

**NESHOBA COUNTY BOARD OF SUPERVISORS
EMERGENCY ROAD AND BRIDGE REPAIR FUND PROJECT NO.
ERBR-STP/BR-0050(35)BO**

ADVERTISEMENT FOR BID

Sealed bids or electronic bids will be received by the Board of Supervisors of Neshoba County in Philadelphia, Mississippi until 1:30PM on June 03, 2019. Sealed bids will be received until the designated date and time at the Neshoba County Courthouse in Philadelphia, Mississippi. Electronic bids will be received until the designated date and time via electronic bid submission through Quest CDN for a \$25 fee. All bids will be thereafter publicly opened for the CONSTRUCTION OF 0.180 MILES OF BOX BRIDGE AND PAVED ROADWAY APPROACHES ON COUNTY ROAD 628 IN NESHOBA COUNTY, MISSISSIPPI being known as Emergency Road and Bridge Repair Fund Project No. ERBR-STP/BR-0050(35)B.

Contract Time: 75 Working Days

The award, if made, will be made to the lowest qualified bidder on the basis of the published quantities.

The Board of Supervisors hereby notifies all bidders that it will affirmatively insure that, in any contract entered into pursuant to this advertisement, minority business enterprises will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

Plans and specifications are on file in the Office of the Chancery Clerk of Neshoba County and the County Engineer's office. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured from Thomas M. (Marty). Crowder, P.E., Engineer for Neshoba County, Mississippi, c/o Crowder Engineering & Surveying, Inc., P. O. Box 1209, Ackerman, MS 39735 (662-285-2062). The Cost is fifty dollars (\$50.00) for printed plans and fifty dollars (\$50.00) for the printed proposal, non-refundable. Plans and Proposals may also be downloaded electronically for a non-refundable fee of \$25.00 by providing QuestCDN Project Number 6289124 on the Project Search Page on the Quest website www.questcdn.com.

To bid electronically, contact QuestCDN at 1-952-233-1632 or info@questcdn.com for assistance with electronic bidding and starting a free membership.

Certified check or bid bond for five percent (5%) of the total bid, made payable to Neshoba County and the State of Mississippi must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid, and such proposal will not be considered in making the award.

Date: April 01, 2019

/s/ Allen White
Allen White, President
Neshoba County Board of Supervisors

Publish: April 24, 2019
May 01, 2019

PROJECT NO. ERBR-STP/BR-0050(35)BO
NESHOMA COUNTY, MISSISSIPPI

For the Construction of: 0.180 miles of BOX BRIDGE AND PAVED ROADWAY APPROACHES on County Road 628 in Neshoba County, Mississippi known as Emergency Road and Bridge Repair
Fund Project No. **ERBR-STP/BR-0050(35)BO**

I (We) agree to complete the entire project within 75 Working Days.

SPECIAL NOTICE TO BIDDERS
BIDS WILL NOT BE CONSIDERED UNLESS BOTH UNIT PRICES AND ITEM TOTALS ARE ENTERED

Ref. No.	Pay Item No.	Description	Approx. Quantity	Unit	Unit Price		Item Total	
					Dollars	Cents	Dollars	Cents
ROADWAY ITEMS								
1	S-200-A	MOBILIZATION	1.000	LS				
2	S-201-A	CLEARING AND GRUBBING	1.000	LS				
3	S-202-B	REMOVAL OF BRIDGE STA. 14+39	1.000	UN				
4	S-202-D	REMOVAL HMA AND/OR DBST SURFACING	1.689.000	SY				
5	S-203-A	UNCLASSIFIED EXCAVATION(FM)	1.381.000	CY				
6	S-203-E1	BORROW EXCAVATION (FME) (CONTRACTOR FURNISHED) (CLASS 9)	4.189.000	CY				
7	S-206-A	STRUCTURE EXCAVATION	942.000	CY				
8	S-304-A	GRANULAR MATERIAL (LVM) (CLASS 3, GROUP B)	1.224.000	CY				
9	S-310-A-1	SIZE 1 STABILIZER AGGREGATE, COARSE (LVM)	250.000	CY				
10	S-403-A	HOT MIX ASPHALT, MT, 9.5 mm	197.000	TON				
11	S-403-A	HOT MIX ASPHALT, MT, 12.5 mm	548.000	TON				
12	S-408-A	ASPHALT FOR PRIME COAT	924.000	GAL				
13	S-607-A	ROADWAY CONSTRUCTION STAKING	1.000	LS				
14	S-617-A	RIGHT-OF-WAY MARKERS (TYPE I)	18.000	EA				
15	S-618-A	MAINTENANCE OF TRAFFIC	1.000	LS				
16	S-618-B	ADDITIONAL CONSTRUCTION SIGNS	0.000	SF	10.00			0.00

Ref. No.	Pay Item No.	Description	Approx. Quantity	Unit	Unit Price		Item Total	
					Dollars	Cents	Dollars	Cents
17	S-621-C	4" WIDE THERMOPLASTIC EDGE STRIPE (CONT. WHITE)(90 mils)	0.360	MI				
18	S-621-E-1	4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW)(120 mils)	1,900.000	LF				
19	S-627-L	TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	25.000	EA				
20	907-247-A	TEMPORARY STREAM DIVERSION	1.000	EA				
					Subtotal Roadway Items			
EROSION CONTROL ITEMS								
21	901-S-212-A	AGRICULTURAL LIMESTONE	3.480	TON				
22	S-212-B	COMMERCIAL FERTILIZER (13-13-13)	1.740	TON				
23	S-212-F	AMMONIUM NITRATE	0.174	TON				
24	S-214-A	SEEDING	1.740	AC				
25	S-215-A	VEGETATIVE MATERIALS FOR MULCH	3.480	TON				
26	901-S-224-A	SOIL REINFORCING MAT	916.000	SY				
27	S-226-A	SOLID SODDING	200.000	SY				
28	S-227-A	EXCELSIOR BLANKET	1,000.000	SY				
29	S-233-A	TEMPORARY SILT FENCE (TYPE I) (AOS 0.15-0.84)	3,095.000	LF				
30	S-815-A	LOOSE RIPRAP, (SIZE 300 LB.)	241.000	TON				
31	S-815-E	GEOTEXTILE UNDER LOOSE RIPRAP (TYPE V) (AOS 0.21-0.43)	356.000	SY				
32	907-237-A	WATTLES, 20 INCH	800.000	LF				
					Subtotal Erosion Control Items			

Ref. No.	Pay Item No.	Description	Approx. Quantity	Unit	Unit Price		Item Total	
					Dollars	Cents	Dollars	Cents
BOX BRIDGE ITEMS								
33	901-S-804-B	BOX BRIDGE CONCRETE, CLASS "BB"	262.800	CY				
34	S-805-A	REINFORCEMENT	50,282.000	LBS				
					Subtotal Box Bridge Items			
					Total Bid			

SPECIMEN
NOT FOR BIDDING