

SIMPSON COUNTY BOARD OF SUPERVISORS

SECTION 900

NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Simpson County, Mississippi at the Simpson County Courthouse, Mendenhall, Mississippi, until 9:00 a.m. on the 13th day of May, 2019 and shortly thereafter publicly opened for the construction of 0.123 miles of BRIDGE AND APPROACHES on the HEED-NEELY road being known as Project No. ERBR-STP/BR-0064(23)B in Simpson County, Mississippi.

PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS:

ITEM	QUANTITY	UNIT
<u>ROADWAY ITEMS</u>		
MOBILIZATION	LUMP SUM	LS
CLEARING AND GRUBBING	LUMP SUM	LS
REMOVAL OF BRIDGE @ STA. 212+13	1.000	UN
UNCLASSIFIED EXCAVATION (FM)	704.000	CY
BORROW EXCAVATION (F.M.E.)	3,890.000	CY
(CONTRACTOR FURNISHED)(CLASS 9)		
GRANULAR MATERIAL, (LVM),	745.000	CY
(CLASS 5, GROUP C)		
HOT MIX ASPHALT, ST. 12.5mm	139.000	TON
HOT MIX ASPHALT, ST. 25mm	290.000	TON
GUARD RAIL, W BEAM	52.000	LF
GUARD RAIL, BRIDGE END SECTION,	4.000	EA
TYPE I		
GUARD RAIL, TERMINAL END SECTION	4.000	EA
RIGHT OF WAY MARKERS (TYPE II)	12.000	EA
MAINTENANCE OF TRAFFIC	LUMP SUM	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4" WIDE THERMOPLASTIC EDGE STRIPE	0.246	MI
(CONTINUOUS WHITE)(60 MILS)		
4" WIDE THERMOPLASTIC TRAFFIC	1,300.000	LF
STRIPE (CONTINUOUS YELLOW)(90 MILS)		
TWO-WAY YELLOW REFLECTIVE HIGH	13.000	EA
PERFORMANCE RAISED MARKERS		
REFLECTORIZED TRAFFIC OBJECT MARKER	4.00	EA
(ENCAPSULATED LENS)(TYPE 3)		

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	1.5000	TON
COMMERCIAL FERTILIZER (13-13-13)	1.5000	TON
AMMONIUM NITRATE	0.060	TON
SEEDING	0.900	AC
VEGETATIVE MATERIALS FOR MULCH	1.500	TON
SOLID SODDING	200.000	SY
PORTLAND CEMENT CONCRETE PAVED DITCH	4.500	CY
TEMPORARY SILT FENCE (TYPE II)(AOS 0.15-0.84)	2,000.000	LF
LOOSE RIPRAP, 200 LB.	100.00	TON
WATTLES, 20"	300.00	LF

BRIDGE ITEMS:

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14" PRESTRESSED CONCRETE PILING	760.000	LF
18" PRE-FORMED PILE HOLES	200.000	LF
40' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR	18.000	EA
40' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR	6.000	EA
PRECAST CONCRETE BARRIER RAIL	240.000	LF
31.17' PRECAST CONCRETE CAP, INTERMEDIATE UNIT, CONCRETE PILE	2.000	EA
31.17' PRECAST CONCRETE CAP, END UNIT, CONCRETE PILE	2.000	EA
9.17 PRECAST CONCRETE WING	4.000	EA
LOOSE RIPRAP, 300 LB.	295.000	TON
GEOTEXTILE UNDER LOOSE RIPRAP TYPE V, AOS 0.21-0.43	680.000	SY

CONTRACT TIME: 80 Working Days

BASIS OF AWARD

The award, if made, will be to the lowest qualified bidder on the basis of the published quantities.

The attention of the BIDDER is directed to the State and Federal laws governing selection of and employment of labor.

The Board of Supervisors hereby notified all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement minority business enterprise will be afforded full

opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for this award.

PLANS AND SPECIFICATIONS are on file at the office of the Project Engineer. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured from Wolverton Engineering, Inc., Project Engineer, at 57 Wolverton Drive, Collins, Mississippi. The Cost is one hundred dollars (\$ 100.00) for plans and one hundred dollars (\$ 100.00) for the proposal non –refundable.

Certified check or bid bond for five percent (%5) of the total bid, made payable to Simpson County and the State of Mississippi must accompany each proposal.

Bidders are hereby notified that any proposal accompanied the letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Mickey Berry, President
Simpson County Board of Supervisors

Advertise: April 10, 2019
April 17, 2019