

SECTION 901

ADVERTISEMENT

Winston County, Mississippi
Russell Road Bridge Replacement

MDOT Project No. CHBP-0080-00(29) 108130-70100

State Aid Project No. STP/BR-0080(33)B

The Board of Supervisors of Winston County, Mississippi will receive bids for the construction of the Russell Road Bridge Replacement Project, MDOT Project No. CHBP-0080-00(29) 108130-70100 and State Aid Project No. STP/BR-0080(33)B, no later than 10:00 A.M., Local Time, September 20, 2019, at the Winston County Courthouse located at 115 South Court Ave., Louisville, MS 39339. All bids so received will be publicly opened and read aloud.

The work shall consist essentially of the following items:

Construction of a precast concrete bridge and paved approaches, and other related items of work required to complete the project as shown and specified in the Construction Plans and Contract Documents.

The above general outline of features of the work does not in any way limit the responsibility of the contractor to perform all work and furnish all labor, equipment and materials required by the specifications and the drawings referred to therein.

The attention of bidders is directed to the Contract Provisions governing selection and employment of labor. Minimum wage rates for Federal-Aid projects have been predetermined by the Secretary of Labor and are subject to Public Law 87-581 Work Hours Act of 1962, as set forth in the Contract Provisions.

The Board of Supervisors of Winston County hereby notifies all Bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, disadvantaged and women's business enterprises will be afforded the full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

The award of this contract will be contingent upon the Contractor satisfying the DBE/WBE requirements.

The contract Documents are on file and may be examined at the following locations:

1. Office of the Chancery Clerk, 115 South Court Ave., Louisville, Mississippi 39339
2. Kemp Associates, LLC, 11 East Main Street, Noxapater, Mississippi 39346, 662-724-2303

All documents required for bidding purposes may be obtained from Kemp Associates, LLC, 11 East Main Street, Noxapater, Mississippi 39346, 662-724-2303. A non-refundable deposit of \$150.00 is required at the time of request for Construction Drawings and Contract Documents.

Each bid shall be accompanied by a Cashier's check, Certified Check on a solvent bank or a Bidder's Bond issued by a Surety Company licensed to operate in the State of Mississippi, in the amount of five percent (5%) of the total bid price, payable to the Winston County Board of Supervisors as bid security. Bidders shall also submit a current financial statement, if requested by the County. The successful bidder will be required to furnish a Performance Bond and a Payment bond each in the amount of one hundred percent (100%) of the contract amount. NO STRIPPED PROPOSALS WILL BE ACCEPTED.

The proposal and contract documents in its entirety shall be submitted in a sealed envelope and deposited with the Chancery Clerk, 115 South Court Avenue, Louisville, Mississippi prior to the hour and date above designated.

Bidders choosing to submit electronically are required to contact the Winston County Board of Supervisors at 662-773-3631 for information regarding electronic bidding requirements.

Work to be performed shall be in accordance with the “Mississippi Standard Specifications for State Aid Road and Bridge Construction, 2004 Edition” and/or the “Mississippi Standard Specifications for Road and Bridge Construction, 2017 Edition”, together with all amendments and/or special provisions and/or addenda to the standards duly approved and adopted, unless otherwise noted in these specifications.

The attention of Bidders is directed to the provisions of Section S-102 pertaining to bidding requirements and conditions.

THE BOARD OF SUPERVISORS, WINSTON
COUNTY, MISSISSIPPI

BY Luke Parkes
President
Board of Supervisors, Winston County

Publish in Clarion-Ledger:
(Due by (8/16/19/10:00 am)

(Date, 8/21/19)

(Date, 8/28/19)

SECTION 902
PROPOSAL SHEET (2-A)

PROJECT NO. STP/BR-0080(33)B
WINSTON COUNTY, MISSISSIPPI

For the construction of: BRIDGE REPLACEMENT AND PAVED APPROACHES on 0.095 mile(s) of county road known as RUSSELL ROAD in Winston County, Mississippi under Surface Transportation Program Project No. STP/BR-0080(33)B.

I (We) agree to complete the entire project within 60 Working Days.

SPECIAL NOTICE TO BIDDERS

BIDS WILL NOT BE CONSIDERED UNLESS BOTH UNIT PRICES AND ITEM TOTALS ARE ENTERED

Ref. No.	Pay Item No.	Description	Approx. Quantity	Unit
Roadway Items				
1	S-200-A	MOBILIZATION	Lump Sum	LS
2	S-201-A	CLEARING AND GRUBBING	Lump Sum	LS
3	S-202-B	REMOVAL OF PRECAST BRIDGE @ STA. 67+86.00	1.000	UN
4	S-202-D	REMOVAL OF HMA AND/OR DBST SURFACING	150.000	SY
5	S-203-H	EXCESS EXCAVATION (LVM)	265.000	CY
6	S-304-A	GRANULAR MATERIAL (LVM), (CLASS 9, GROUP C)	1,080.000	CY
7	S-310-A-1	SIZE (I) STABILIZER AGGREGATE, COARSE	10.000	CY
8	S-403-A	HOT MIX ASPHALT, (ST) (09.5mm)	98.000	TON
9	S-403-A	HOT MIX ASPHALT, (ST) (19.0mm)	76.000	TON
10	S-603-C-A	18" REINFORCED CONCRETE PIPE, CLASS III	32.000	LF
11	S-603-C-A	24" REINFORCED CONCRETE PIPE, CLASS III	32.000	LF
12	S-603-C-B	18" REINFORCED CONCRETE PIPE, END SECTION	2.000	EA
13	S-603-C-B	24" REINFORCED CONCRETE PIPE, END SECTION	2.000	EA
14	S-606-B	GUARD RAIL, "W" BEAM	175.000	LF
15	S-606-D	GUARD RAIL, BRIDGE END SECTION, TYPE "I" THRIE BEAM	4.000	EA
16	S-606-E	GUARD RAIL, TERMINAL END SECTION	4.000	EA
17	S-607-A	ROADWAY CONSTRUCTION SURVEYING	Lump Sum	LS

SECTION 902
PROPOSAL SHEET (2-B)

Ref. No.	Pay Item No.	Description	Approx. Quantity	Unit
18	S-617-A	RIGHT-OF-WAY MARKERS (TYPE II)	4.000	EA
19	S-618-A	MAINTENANCE OF TRAFFIC	Lump Sum	LS
20	S-618-B	ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
21	S-621-C	4" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (90 MILS)	0.189	MI
22	S-621-D	4" WIDE THERMOPLASTIC TRAFFIC STRIPE (SKIP YELLOW) (120 MILS)	0.095	MI
23	S-621-E-1	4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (120 MILS)	110.000	LF
24	S-627-L	TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	7.000	EA
25	S-630-C	REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA
Erosion Control Items				
26	901-S-212-A	AGRICULTURAL LIMESTONE	1.400	TON
27	S-212-B	COMMERCIAL FERTILIZER (13-13-13)	0.350	TON
28	S-212-F	AMMONIUM NITRATE	0.105	TON
29	S-214-A	SEEDING	0.700	AC
30	S-215-A	VEGETATIVE MATERIALS FOR MULCH	1.400	TON
31	S-226-A	SOLID SODDING	600.000	SY
32	S-227-A	EXCELSIOR BLANKET	1,350.000	SY
33	S-233-A	TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	1,542.000	LF
34	S-235-A	TEMPORARY EROSION CHECKS	50.000	BL
35	S-815-A	LOOSE RIPRAP, 200 LB.	52.000	TON
36	S-815-E	GEOTEXTILE UNDER RIPRAP, TYPE V, (AOS 0.21-0.43)	104.000	SY
37	907-237-A	WATTLES, 20"	360.000	LF
				Subt

SECTION 902
PROPOSAL SHEET (2-C)

Ref. No.	Pay Item No.	Description	Approx. Quantity	Unit
Bridge Items				
38	S-803-A	TEST PILE	2.000	EA
39	S-803-B	CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
40	S-803-C	14" PRESTRESSED CONCRETE PILING	760.000	LF
41	S-803-F	18" PRE-FORMED PILE HOLES	556.000	LF
42	S-806-A	19' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR	12.000	EA
43	S-806-A	40' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR	6.000	EA
44	S-806-C	19' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR	4.000	EA
45	S-806-C	40' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR	2.000	EA
46	S-806-G	PRECAST CONCRETE BARRIER RAIL	156.000	LF
47	S-806-I	31.33' PRECAST CONCRETE CAP, INTERMEDIATE UNIT, CONCRETE PILE,	2.000	EA
48	S-806-J	31' PRECAST CONCRETE CAP, END UNIT, CONCRETE PILE,	2.000	EA
49	S-806-M	9.25' PRECAST CONCRETE WING	4.000	EA
50	S-815-A	LOOSE RIPRAP, 300 LB.	82.000	TON
51	S-815-E	GEOTEXTILE UNDER RIPRAP, TYPE V, (AOS 0.21-0.43)	173.000	SY