

Section 901

ADVERTISEMENT

Jefferson Davis County, Mississippi
Bass – Burkett Road Bridge Replacements

MDOT Project No. CHBP-0290-00(013) 108132/701000 & CHBP-0290-00(014) 108132/702000
State Aid Project No. STP/BR-0290(13)BO

The Board of Supervisors of Jefferson Davis County, Mississippi will receive bids for the construction of the Bass – Burkett Road Bridge Replacement Project, MDOT Project No. CHBP-0290-00(013) 108132/701000 & CHBP-0290-00(014) 108132/702000 and State Aid Project No. STP/BR-0290(13)BO, no later than 10:00 A.M., Local Time, August 19th, 2019, at the Jefferson Davis County Administrative Building located at 2426 Pearl Ave., Prentiss, MS 39474. All bids so received will be publicly opened and read aloud.

The work shall consist essentially of the following items:

Precast concrete bridge and approaches, poured in place box bridge, roadway construction, paving and other related items of work required to complete the project as shown and specified in the Contract Documents.

The above general outline of features of the work does not in any way limit the responsibility of the contractor to perform all work and furnish all plant, labor, equipment and materials required by the specifications and the drawings referred to therein.

The attention of bidders is directed to the Contract Provisions governing selection and employment of labor. Minimum wage rates for Federal-Aid projects have been predetermined by the Secretary of Labor and are subject to Public Law 87-581 Work Hours Act of 1962, as set forth in the Contract Provisions.

The Board of Supervisors of Jefferson Davis County hereby notifies all Bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, disadvantaged and women's business enterprises will be afforded the full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

The award of this contract will be contingent upon the Contractor satisfying the DBE/WBE requirements.

The contract Documents are on file and may be examined at the following locations:

1. Office of the Chancery Clerk of Jefferson Davis County, Prentiss, Mississippi 39474.
2. Dungan Engineering, PA, 1574 Highway 98 East, Columbia, Mississippi 39429, 601-731-2600

All documents required for bidding purposes may be obtained from Dungan Engineering, PA, 1574 Highway 98 East, Columbia, MS 39429, 601-731-2600. A non-refundable deposit of \$200.00 is required at the time of request for Construction Drawings and Contract Documents.

Each bid shall be accompanied by a Cashier's check, Certified Check on a solvent bank or a Bidder's Bond issued by a Surety Company licensed to operate in the State of Mississippi, in the amount of five percent (5%) of the total bid price, payable to the Jefferson Davis County Board of Supervisors as bid security. Bidders shall also submit a current financial statement, if requested by the County. The successful bidder will be required to furnish a Performance Bond and a Payment bond each in the amount of one hundred percent (100%) of the contract amount.
NO STRIPPED PROPOSALS WILL BE ACCEPTED.

The proposal and contract documents in its entirety shall be submitted in a sealed envelope and deposited at the Jefferson Davis County Administrative Building located at 2426 Pearl Ave., Prentiss, MS 39474 prior to the hour and date above designated.

Work to be performed shall be in accordance with the “Mississippi Standard Specifications for State Aid Road and Bridge Construction, 2004 Edition”, together with all amendments and/or special provisions and/or addenda to the standards duly approved and adopted, unless otherwise noted in these specifications.

The attention of Bidders is directed to the provisions of Section S-102 pertaining to bidding requirements and conditions.

THE BOARD OF SUPERVISORS, JEFFERSON DAVIS
COUNTY, MISSISSIPPI

BY Macon “Corky” Holliman
President
Board of Supervisors, Jefferson Davis County

Publish in Clarion-Ledger:

Tuesday, July 16, 2019

Tuesday, July 23, 2019

SECTION 902
PROPOSAL SHEET (2-A)

PROJECT NO. STP/BR-0290(13)BO
JEFFERSON DAVIS COUNTY, MISSISSIPPI

For the construction of: BRIDGE REPLACEMENT on 0.662 mile(s) of county road known as BASS - BURKETT ROAD in Jefferson Davis County, Mississippi under Surface Transportation Program Project No. STP/BR-0290(13)BO.

I (We) agree to complete the entire project within 150 Working Days.

SPECIAL NOTICE TO BIDDERS

BIDS WILL NOT BE CONSIDERED UNLESS BOTH UNIT PRICES AND ITEM TOTALS ARE ENTERED

Ref. No.	Pay Item No.	Description	Approx. Quantity	Unit	Unit Price		Item Total	
					Dollars	Cents	Dollars	Cents
Roadway Items								
1	S-200-A	MOBILIZATION	Lump Sum	LS	XXXXXXXXXX	XXXXXXXXXX		
2	S-201-A	CLEARING AND GRUBBING	Lump Sum	LS	XXXXXXXXXX	XXXXXXXXXX		
3	S-202-B	REMOVAL OF BRIDGE AT STATION 13+99	1.000	UN				
4	S-202-B	REMOVAL OF BRIDGE AT STATION 36+76	1.000	UN				
5	S-202-E	REMOVAL OF PIPE (ALL SIZES)	369.000	LF				
6	S-203-A	UNCLASSIFIED EXCAVATION (FM)	6,735.000	CY				
7	S-203-E1	BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 7)	7,390.000	CY				
8	S-203-F	CHANNEL EXCAVATION (FM)	680.000	CY				
9	S-206-A	STRUCTURE EXCAVATION	830.000	CY				
10	247-A	TEMPORARY STREAM DIVERSION	1.000	EA				
11	S-304-A	GRANULAR MATERIAL (LVM) , (CLASS 6, GROUP C)	6,850.000	CY				
12	S-310-A-1	SIZE II STABILIZER AGGREGATE, COARSE	260.000	CY				
13	S-310-D	MIXING, SHAPING AND COMPACTION	9,778.000	SY				
14	S-403-A	HOT MIX ASPHALT, ST 9.5 MM	745.000	TON				
15	S-403-A	HOT MIX ASPHALT, ST 19 MM	1,551.000	TON				
16	S-408-A	ASPHALT FOR PRIME COAT (EA-1)	3,291.000	GAL				
17	S-601-B	CLASS "B" STRUCTURAL CONCRETE, MINOR STRUCTURES	0.246	CY				
18	S-603-C-A	18" REINFORCED CONCRETE PIPE, CLASS III	336.000	LF				

SECTION 902
PROPOSAL SHEET (2-B)

PROJECT NO. STP/BR-0290(13)BO
JEFFERSON DAVIS COUNTY, MISSISSIPPI

Ref. No.	Pay Item No.	Description	Approx. Quantity	Unit	Unit Price		Item Total	
					Dollars	Cents	Dollars	Cents
19	S-603-C-A	24" REINFORCED CONCRETE PIPE, CLASS III	168.000	LF				
20	S-603-C-D	44" X 27" REINFORCED CONCRETE ARCH PIPE, CLASS III	48.000	LF				
21	S-603-C-E	44" X 27" REINFORCED CONCRETE ARCH PIPE, END SECTION	2.000	EA				
22	S-606-B	GUARD RAIL, W-BEAM	275.000	LF				
23	S-606-D	GUARD RAIL, BRIDGE END SECTION, TYPE I THRIE-BEAM	4.000	EA				
24	S-606-E	GUARD RAIL, TERMINAL END SECTION	4.000	EA				
25	S-607-A	ROADWAY CONSTRUCTION SURVEYING	Lump Sum	LS	XXXXXXXXXX	XXXXXXXXXX		
26	S-617-A	RIGHT-OF-WAY MARKERS (TYPE I)	36.000	EA				
27	S-618-A	MAINTENANCE OF TRAFFIC	Lump Sum	LS	XXXXXXXXXX	XXXXXXXXXX		
28	S-618-B	ADDITIONAL CONSTRUCTION SIGNS	0.000	SF	10	00	0	00
29	S-621-C	4" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (60 MILS)	1.246	MI				
30	S-621-E-1	4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (90 MILS)	7,000.000	LF				
31	S-621-G-1	THERMOPLASTIC DETAIL STRIPE (4" EQUIVALENT LENGTH) (WHITE) (60 MILS)	520.000	LF				
32	S-621-G-2	THERMOPLASTIC DETAIL STRIPE (4" EQUIVALENT LENGTH) (YELLOW) (90 MILS)	150.000	LF				
33	S-621-H-2	THERMOPLASTIC LEGEND (WHITE) (120 MILS)	36.000	SF				
34	S-627-L	TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	75.000	EA				
35	S-630-A	REFLECTORIZED TRAFFIC WARNING SIGN (ENCAPSULATED LENS)	6.000	EA				
36	S-630-B	REFLECTORIZED TRAFFIC REGULATORY SIGN (ENCAPSULATED LENS)	1.000	EA				

SECTION 902
PROPOSAL SHEET (2-C)

PROJECT NO. STP/BR-0290(13)BO
JEFFERSON DAVIS COUNTY, MISSISSIPPI

Ref. No.	Pay Item No.	Description	Approx. Quantity	Unit	Unit Price		Item Total	
					Dollars	Cents	Dollars	Cents
37	S-630-C	REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA				
Subtotal Roadway Items								
Erosion Control Items								
38	901-S-212-A	AGRICULTURAL LIMESTONE	16.000	TON				
39	S-212-B	COMMERCIAL FERTILIZER (13-13-13)	8.000	TON				
40	S-212-F	AMMONIUM NITRATE	0.800	TON				
41	S-214-A	SEEDING	8.000	AC				
42	S-215-A	VEGETATIVE MATERIALS FOR MULCH	16.000	TON				
43	S-226-A	SOLID SODDING	2,198.000	SY				
44	S-229-A	PORTLAND CEMENT CONCRETE PAVED DITCH	239.460	CY				
45	S-231-A	EROSION CONTROL FABRIC	1,200.000	SY				
46	S-233-A	TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	7,020.000	LF				
47	237-A	WATTLES, 20"	860.000	LF				
48	S-815-A	LOOSE RIPRAP, 200 LB.	275.000	TON				
49	S-815-E	GEOTEXTILE UNDER RIPRAP, TYPE V, AOS 0.21-0.43	535.000	SY				
Subtotal Erosion Control Items								
Bridge Items								
50	S-803-A	TEST PILE	2.000	EA				
51	S-803-B	CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA	4,000	00	0	00
52	S-803-C	14" PRESTRESSED CONCRETE PILING	920.000	LF				
53	S-806-A	31' PRECAST CONCRETE SLAB UNIT, 3'-6" INTERIOR	24.000	EA				
54	S-806-A	40' PRECAST CONCRETE SLAB UNIT, 3'-6" INTERIOR	6.000	EA				
55	S-806-C	31' PRECAST CONCRETE SLAB UNIT, 3'-6" EXTERIOR	8.000	EA				

PROPOSAL SHEET (2-D)

PROJECT NO. STP/BR-0290(13)BO
JEFFERSON DAVIS COUNTY, MISSISSIPPI

Ref. No.	Pay Item No.	Description	Approx. Quantity	Unit	Unit Price		Item Total	
					Dollars	Cents	Dollars	Cents
56	S-806-C	40' PRECAST CONCRETE SLAB UNIT, 3'-6" EXTERIOR	2.000	EA				
57	S-806-G	PRECAST CONCRETE BARRIER RAIL	328.000	LF				
58	S-806-I	31' PRECAST CONCRETE CAP, INTERMEDIATE UNIT, CONCRETE PILE	2.000	EA				
59	S-806-I	31'-4" PRECAST CONCRETE CAP, INTERMEDIATE UNIT, CONCRETE PILE,	2.000	EA				
60	S-806-J	31' PRECAST CONCRETE CAP, END UNIT, CONCRETE PILE,	2.000	EA				
61	S-806-M	9.25' PRECAST CONCRETE WING	4.000	EA				
62	S-815-A	LOOSE RIPRAP, 300 LB.	154.000	TON				
63	S-815-E	GEOTEXTILE UNDER RIPRAP, TYPE V, AOS 0.21-0.43	384.000	SY				
Subtotal Bridge Items								
Box Bridge Items								
64	901-S-804-B	BOX BRIDGE CONCRETE, CLASS "BB"	142.920	CY				
65	S-805-A	REINFORCEMENT	25,777.000	LB				
Subtotal Box Bridge Items								
Total Bid								