

OFFICE OF STATE AID ROAD CONSTRUCTION  
MISSISSIPPI DEPARTMENT OF TRANSPORTATION  
AND  
ATTALA COUNTY BOARD OF SUPERVISORS

SECTION 900

NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Attala County, Mississippi at the Attala County Chancery Clerk Building, Kosciusko, Mississippi, until 9:30 am on the 20th day of May, 2019 and shortly thereafter publicly opened for the construction of 0.226 miles of REPLACE BRIDGE AND APPROACHES on the HIGHWAY 407 being known as Project No. ERBR-STP/BR-0722(7)BO in Attala County, Mississippi.

PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS:

ITEM	QUANTITY	UNIT
<u>ROADWAY ITEMS:</u>		
MOBILIZATION	Lump Sum	LS
CLEARING AND GRUBBING	Lump Sum	LS
REMOVAL OF BRIDGE @ STA. 56+09	1.000	UN
REMOVAL OF EXISTING ASPHALT PAVEMENT (ALL DEPTHS)	2,053.000	SY
UNCLASSIFIED EXCAVATION (FM)	3,272.000	CY
BORROW EXCAVATION (FME)	9,140.000	CY
CRUSHED STONE	2,456.000	TON
MIXING, SHAPING AND COMPACTION	2,257.000	SY
HOT MIX ASPHALT, (ST) (9.5 MM)	345.000	TON
ASPHALT FOR PRIME COAT (EA-1)	905.000	GAL
18" ALUMINUM COATED CORRUGATED METAL PIPE, 12 GAGE, 2 2/3" X 1/2"	70.000	LF
18" ALUMINUM COATED CORRUGATED METAL END SECTION, 12 GAGE	2.000	EA
GUARD RAIL, "W" BEAM	175.000	LF
GUARD RAIL, BRIDGE END SECTION, TYPE "I" THRIE BEAM	4.000	EA
GUARD RAIL, TERMINAL END SECTION	4.000	EA
ROADWAY CONSTRUCTION SURVEYING	Lump Sum	LS
BRIDGE CONSTRUCTION SURVEYING	Lump Sum	LS
RIGHT-OF-WAY MARKERS (TYPE I)	8.000	EA
MAINTENANCE OF TRAFFIC	Lump Sum	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (60 MILS)	0.455	MI

SECTION 900  
PROJECT NO. ERBR-STP/BR-0722(7)BO  
ATTALA COUNTY

---

4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (90 MILS)	0.455	MI
TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	17.000	EA
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	8.260	TON
COMMERCIAL FERTILIZER (13:13:13)	1.860	TON
AMMONIUM NITRATE	0.410	TON
SEEDING	6.200	AC
VEGETATIVE MATERIALS FOR MULCH	18.600	TON
EXCELSIOR BLANKET	300.000	SY
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15 - 0.84)	2,960.000	LF
LOOSE RIPRAP, 200 LB	350.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, AOS 0.21 - 0.43	420.000	SY
WATTLES, 20"	920.000	LF

BRIDGE ITEMS:

16" TEST PILE	2.000	EA
18" TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
16" PRESTRESSED CONCRETE PILING	2,050.000	LF
18" PRESTRESSED CONCRETE PILING	900.000	LF
24" PRE-FORMED PILE HOLES	2,551.000	LF
PILING CUTOFF (16" CONCRETE PILE)	0.000	EA
PILING CUTOFF (18" CONCRETE PILE)	0.000	EA
BRIDGE CONCRETE, CLASS "A"	413.450	CY
40' PRESTRESSED CONCRETE BEAM TYPE I+2	596.250	LF
80' PRESTRESSED CONCRETE BEAM TYPE III	797.500	LF
100' PRESTRESSED CONCRETE BEAM TYPE IV	498.750	LF
REINFORCEMENT	75,787.000	LB
CONCRETE RAILING	758.840	LF
LOOSE RIPRAP, 300 LB	910.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, AOS 0.21 - 0.43	1,911.000	SY

SECTION 900  
PROJECT NO. ERBR-STP/BR-0722(7)BO  
ATTALA COUNTY

---

NOTICE TO CONTRACTORS:

CONTRACT TIME                      150 WORKING DAYS

BASIS OF AWARD

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

The attention of the BIDDER is directed to the State and Federal laws governing selection of and employment of labor.

The Board of Supervisors hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, minority business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

PLANS AND PROPOSALS may be secured from J. Christian Gardner, County Engineer for Attala County, Mississippi, P.O. Drawer 1197, Kosciusko. The Cost is fifty dollars (\$50.00) for plans and fifty dollars (\$50.00) for the proposal, non-refundable.

Certified check or bid bond for five percent (5%) of the total bid, made payable to Attala County and the State of Mississippi must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Bobby Lindsay, President  
Attala County Board of Supervisors