

NOTICE OF ADVERTISEMENT

**EMERGENCY ROAD AND BRIDGE REPAIR FUND PROJECT
PROJECT NO. ERBR-STPBR-0747(6)B
COONTAIL ROAD
MONROE COUNTY, MISSISSIPPI**

NOTICE TO CONTACTORS: Project No. ERBR-STPBR-0747(6)B Monroe County, MS. The Board of Supervisors of Monroe County, MS will receive bids for the construction of **0.268 miles of Bridge and Approaches to Replace Bridge No. 100 on Coontail Road.** This project is funded by Mississippi Infrastructure Modernization Act of 2018's Emergency Road & Bridge Repair Fund. Sealed bids or electronic bids will be received until **9:00 AM on the 5th day of August, 2019** and shortly thereafter publicly opened. **Sealed bids** will be received at the **Monroe County Chancery Building, 201 West Commerce Street, Aberdeen, MS** or **electronic bids** will be received via electronic online bid submission through **www.cceplanroom.com**. Plans, specifications & contract documents are on file in the Office of the Chancery Clerk of Monroe County, Mississippi. Plans, specifications & contract documents may be viewed and/or secured from **Kyle Strong, Engineer of Record** of Cook Coggin Engineers, Inc., at **www.cceplanroom.com** upon payment of \$100.00, which is non-refundable. Plans, specifications & contract documents may also be downloaded electronically for an additional \$25 fee by Bidders for electronic bidding purposes **only**. Questions regarding electronic bidding shall be directed to Plan House Printing at (662) 407-0193. Project information is also available on the website of the Mississippi Office of State Aid Road Construction at **www.osarc.ms.gov/bid-calendar-erbf**. The award, if made, will be made to the lowest qualified bidder on the basis of qualified quantities. The Board of Supervisors hereby notifies all bidders that it will affirmatively ensure that minority business enterprises will be afforded full opportunity to submit bids and will not be discriminated against on the grounds of race, color, or national origin in consideration of the award. Bids will be accepted only under the name of the Bidder whose name appears on the official list of Planholders maintained by the Engineer of Record. Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

William "Billy" Kirkpatrick, President
Monroe County Board of Supervisors

Publish: *July 3rd and July 10th, 2019*

BID SCHEDULE

Each bid item unit price shall include sales tax and all other applicable taxes and fees.

Bidder acknowledges that (1) each Unit Price Bid includes an amount considered by Bidder to be adequate to cover Contractor's overhead and profit for each separately identified item, (2) estimated quantities are not guaranteed and are solely for the purpose of comparison of Bids, and (3) final payment for all Unit Price Bid Items will be based on actual quantities, determined as provided in the Contract Documents.

Write/Type unit prices and bid prices, as clearly as possible, in number format.

Item No.	Item Description	Estimated Quantity	Unit
ERBR-STPBR-0747(6)B COONTAIL ROAD			
BASE BID ITEMS			
Roadway Items			
S-200-A	Mobilization	1.000	LS
S-201-A	Clearing & Grubbing	1.000	LS
S-202-B	Removal of Existing Bridge	1.000	UNIT
S-202-D	Removal of Asphalt, All Depths	2,883.000	SY
S-203-A	Unclassified Excavation (FM)	1,140.000	CY
S-203-E1	Borrow Excavation (FME) (Contractor Furn.) (CI.9)	20,220.000	CY
S-232-A	Geotextile Fabric Stabilization (Type V) (AOS <0.43)	3,242.000	SY
907-260-A005	Utility Work, Sewer	1.000	LS
907-262-A007	Utility Work, Water	1.000	LS
S-304-A	Granular Material (LVM) (Class 5, Group "C")	380.000	CY
S-304-C	Crushed Stone (3/4" & Down) (FM)	1,685.000	CY
S-310-D	Mixing, Shaping and Compaction	3,275.000	SY
S-403-A	Hot Mix Asphalt, ST, 9.5 mm	664.000	TON
S-408-A	Asphalt for Prime Coat (MC-70 or EA-1)	1,146.000	GAL
S-603-C-A	15" Reinforced Concrete Pipe, Class III	40.000	LF
S-603-C-A	18" Reinforced Concrete Pipe, Class III	40.000	LF
S-603-C-A	36" Reinforced Concrete Pipe, Class III	96.000	LF
S-603-C-B	36" Reinforced Concrete Pipe, End Section	2.000	EA

BID SCHEDULE

Item No.	Item Description	Estimated Quantity	Unit
S-606-B	Guardrail "W" Beam	400.000	LF
S-606-D	Guardrail Bridge End Section, Type I, Thrie Beam	4.000	EA
S-606-E	Guardrail, Terminal End Section	4.000	EA
S-607-A	Roadway Construction Surveying	1.000	LS
S-617-A	Right Of Way Markers, Type I	8.000	EA
S-618-A	Maintenance of Traffic	1.000	LS
S-618-B	Additional Construction Signs	-	SF
S-621-C	4" Wide Thermoplastic Edge Stripe (Cont. White) (60 Mils)	0.536	MI
S-621-E-1	4" Wide Thermoplastic Traffic Stripe (Cont. Yellow) (90 Mils)	2,828.000	LF
S-627-L	Two-Way Yellow Reflective High Performance Raised Markers	46.000	EA
S-630-A	Reflectorized Traffic Warning Sign (Encapsulated Lens)	4.000	EA
S-630-C	Reflectorized Traffic Object Marker (Encapsulated Lens) (Type 3)	4.000	EA
S-630-D	Reflectorized Traffic Delineator Sign (Encapsulated Lens)	24.000	EA
Erosion Control Items			
901-S-212-A	Agricultural Limestone	8.000	TON
S-212-B	Commercial Fertilizer (13-13-13)	4.000	TON
S-212-F	Ammonium Nitrate	1.000	TON
S-214-A	Seeding	4.000	AC
S-215-A	Vegetative Materials for Mulch	8.000	TON
S-226-A	Solid Sodding	100.000	SY
S-233-A	Temporary Silt Fence (Type I or II) (AOS 0.15-0.	1,700.000	LF
S-815-A	Loose Riprap, 300 Lb	20.000	TON
S-815-E	Geotextile Under Riprap, Type V, AOS <0.43	100.000	SY
234-F	Turbidity Barrier	675.000	LF
237-A	Wattles, 20"	420.000	LF

BID SCHEDULE

Item No.	Item Description	Estimated Quantity	Unit
Bridge Items 31' - 60' - 110' - 60' - 31' Prestressed Concrete Beam Spans			
S-607-B	Bridge Constuction Surveying	1.00	LS
S-803-A	Test Pile	2.00	EA
S-803-B	Conventional Static Pile Load Test	-	EA
S-803-E	14" Steel Piling	4,030.00	LF
901-S-804-A	Bridge Concrete, Class "A"	433.20	CY
901-S-804-C	31' Prestressed Concrete Beam Type I+2	307.50	LF
901-S-804-C	60' Prestressed Concrete Beam Type III	597.50	LF
901-S-804-C	110' Prestressed Concrete Beam, Type IV	548.75	LF
S-805-A	Reinforcement	63,960.00	LB
S-810-A	Structural Steel	13,077.00	LB
S-813-A	Concrete Railing	582.84	LF
S-815-A	Loose Riprap, 300 Lb	800.00	TON
S-815-E	Geotextile Under Riprap, Type V, AOS <0.43	1,292.00	SY