

NOTICE OF ADVERTISEMENT

**EMERGENCY ROAD AND BRIDGE REPAIR FUND PROJECT
PROJECT NO. ERBR-STPBR-0812(11)B
COUNTY ROAD 407
CHICKASAW COUNTY, MISSISSIPPI**

NOTICE TO CONTACTORS: Project No. ERBR-STPBR-0812(11)B Chickasaw County, MS. The Board of Supervisors of Chickasaw County, MS will receive bids for the construction of **0.279 miles of Site "A" – Box Culvert and Approaches to Replace Bridge No. 149 and Site "B" – Replace Bridge No. 146 with a Prestressed Bridge on County Road 407.** This project is funded by Mississippi Infrastructure Modernization Act of 2018's Emergency Road & Bridge Repair Fund. Sealed bids will be received until **10:00 AM on the 15th day of July, 2019** and shortly thereafter publicly opened at the **Chickasaw County 1st District Office, One Pinson Square, Houston, MS.** Plans, specifications & contract documents are on file in the Office of the Chancery Clerk of Chickasaw County, Mississippi. Plans, specifications & contract documents may be viewed and/or secured from **Carrson Neal, Engineer of Record** of Cook Coggin Engineers, Inc., at www.cceplanroom.com upon payment of \$100.00, which is non-refundable. Project information is also available on the website of the Mississippi Office of State Aid Road Construction at www.osarc.ms.gov/bid-calendar-erbf. The award, if made, will be made to the lowest qualified bidder on the basis of qualified quantities. The Board of Supervisors hereby notifies all bidders that it will affirmatively ensure that minority business enterprises will be afforded full opportunity to submit bids and will not be discriminated against on the grounds of race, color, or national origin in consideration of the award. Bids will be accepted only under the name of the Bidder whose name appears on the official list of Planholders maintained by the Engineer of Record. Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Bill Blissard, President
Chickasaw County Board of Supervisors

Publish: *June 12th and June 19th, 2019*

BID SCHEDULE

Each bid item unit price shall include sales tax and all other applicable taxes and fees.

Bidder acknowledges that (1) each Unit Price Bid includes an amount considered by Bidder to be adequate to cover Contractor's overhead and profit for each separately identified item, (2) estimated quantities are not guaranteed and are solely for the purpose of comparison of Bids, and (3) final payment for all Unit Price Bid Items will be based on actual quantities, determined as provided in the Contract Documents.

Write/Type unit prices and bid prices, as clearly as possible, in number format.

Item No.	Item Description	Estimated Quantity	Unit	Bid Unit Price	Bid Price
ERBR-STPBR-0812(11)BO COUNTY ROAD 407					
BASE BID ITEMS					
Roadway Items					
S-200-A	Mobilization	1.00	LS	\$	\$
S-201-A	Clearing & Grubbing	1.00	LS	\$	\$
S-202-B	Removal of Existing Bridge @ Sta. 26+42	1.00	UN	\$	\$
S-202-B	Removal of Existing Bridge @ Sta. 49+08	1.00	UN	\$	\$
S-202-D	Removal and Relay Riprap (All Sizes)	170.00	SY	\$	\$
S-203-A	Unclassified Excavation (FM)	3,621.00	CY	\$	\$
S-203-H	Excess Excavation (FM)	1,502.00	CY	\$	\$
247-A	Temporary Stream Diversion	1.00	EA	\$	\$
S-304-A	Granular Material (LVM) (Class 5, Group "C")	2,377.00	CY	\$	\$
S-304-A	Granular Material (LVM) (Class 9, Group "B")	2,777.00	CY	\$	\$
S-601-A	Class B Structural Concrete	230.43	CY	\$	\$
S-602-A	Reinforcing Steel	36,985.00	LB	\$	\$
S-603-C-A	18" Reinforced Concrete Pipe, Class III	72.00	LF	\$	\$
S-606-B	Guard Rail, "W" Beam	175.00	LF	\$	\$
S-606-D	Guard Rail, Bridge End Section, Type I Thrie Beam	4.00	EA	\$	\$
S-606-E	Guard Rail, Terminal End Section	4.00	EA	\$	\$
S-607-A	Roadway Construction Surveying	1.00	LS	\$	\$
S-617-A	Right Of Way Markers, Type II	27.00	EA	\$	\$

BID SCHEDULE

Item No.	Item Description	Estimated Quantity	Unit	Bid Unit Price	Bid Price
S-618-A	Maintenance of Traffic	1.00	LS	\$ 10.00	\$ 0.00
S-618-B	Additional Construction Signs	-	SF		\$
S-630-C	Reflectorized Traffic Object Marker (Encapsulated Lens) (Type 3)	4.000	EA		\$
S-630-D	Reflectorized Traffic Deleneator Sign (Encapsulated Lens)	18.00	EA		\$
Erosion Control Items					
901-S-212-A	Agricultural Limestone	4.70	TON	\$	\$
S-212-B	Commercial Fertilizer (13-13-13)	2.35	TON	\$	\$
S-212-F	Ammonium Nitrate	0.60	TON	\$	\$
S-214-A	Seeding	2.35	AC	\$	\$
S-215-A	Vegetative Materials for Mulch	4.70	TON	\$	\$
S-226-A	Solid Sodding	200.00	SY	\$	\$
S-233-A	Temporary Silt Fence (Type I or II) (AOS 0.15-0.84)	1,955.00	LF	\$	\$
237-A	Wattles, 20"	340.00	LF	\$	\$
S-815-A	Loose Riprap, 300 Lb	400.00	TON	\$	\$
S-815-E	Geotextile Under Riprap, Type V, AOS <0.43	740.00	SY	\$	\$
Bridge Items STA. 49+03 - 1 @ 40'; 1 @ 100'; 1 @ 40' Prestressed Concrete Beam Spans					
S-607-B	Bridge Constuction Surveying	1.00	LS	\$	\$
S-803-A	Test Piles	2.00	EA	\$	\$
S-803-B	Conventional Static Pile Load Test	-	EA	\$ \$ 4,000.00	\$ 0.00
S-803-E	14" Steel Piling	1,890.00	LF	\$	\$
S-803-F	18" Pre-formed Pile Holes	1,337.00	LF	\$	\$
901-S-804-A	Bridge Concrete, Class "A"	232.71	CY	\$	\$
901-S-804-C	40' Prestressed Concrete Beam Type I+2	397.50	LF	\$	\$
901-S-804-C	100' Prestressed Concrete Beam Type IV	498.75	LF	\$	\$

BID SCHEDULE

Item No.	Item Description	Estimated Quantity	Unit	Bid Unit Price	Bid Price
S-805-A	Reinforcement	36,455.00	LB	\$	\$
S-813-A	Concrete Railing	360.00	LF	\$	\$
S-815-A	Loose Riprap, 300 Lb	556.00	TON	\$	\$
S-815-E	Geotextile Under Riprap, Type V, AOS <0.43	1,030.00	SY	\$	\$
TOTAL BASE BID					\$