

NOTICE OF ADVERTISEMENT

**EMERGENCY ROAD AND BRIDGE REPAIR FUND PROJECT
PROJECT NO. ERBR-STPBR-0970(6)B
BRADDOCKS STORE-PEOPLES ROAD (COUNTY ROAD 200)
TIPPAH COUNTY, MISSISSIPPI**

NOTICE TO CONTACTORS: Project No. ERBR-STPBR-0970(6)B Tippah County, MS. The Board of Supervisors of Tippah County, MS will receive bids for the construction of **0.104 miles of Bridge and Approaches to Replace Bridge No. 37 on Braddocks Store-Peoples Road (County Road 200)**. This project is funded by Mississippi Infrastructure Modernization Act of 2018's Emergency Road & Bridge Repair Fund. Sealed bids or electronic bids will be received until **10:00 AM on the 28th day of June, 2019** and shortly thereafter publicly opened. **Sealed bids** will be received at the **Tippah County Chancery Building, 101 East Spring Street, Ripley, MS** or **electronic bids** will be received via electronic online bid submission through **www.cceplanroom.com**. Plans, specifications & contract documents are on file in the Office of the Chancery Clerk of Tippah County, Mississippi. Plans, specifications & contract documents may be viewed and/or secured from **Kenneth P. Geno, Jr., Engineer of Record** of Cook Coggin Engineers, Inc., at **www.cceplanroom.com** upon payment of \$100.00, which is non-refundable. Plans, specifications & contract documents may also be downloaded electronically for an additional \$25 fee by Bidders for electronic bidding purposes **only**. Questions regarding electronic bidding shall be directed to Plan House Printing at (662) 407-0193. Project information is also available on the website of the Mississippi Office of State Aid Road Construction at **www.osarc.ms.gov/bid-calendar-erbf**. The award, if made, will be made to the lowest qualified bidder on the basis of qualified quantities. The Board of Supervisors hereby notifies all bidders that it will affirmatively ensure that minority business enterprises will be afforded full opportunity to submit bids and will not be discriminated against on the grounds of race, color, or national origin in consideration of the award. Bids will be accepted only under the name of the Bidder whose name appears on the official list of Planholders maintained by the Engineer of Record. Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Jimmy Gunn, President
Tippah County Board of Supervisors

Publish: *May 15th, 2019 & May 22nd, 2019*

BID SCHEDULE

Each bid item unit price shall include sales tax and all other applicable taxes and fees.

Bidder acknowledges that (1) each Unit Price Bid includes an amount considered by Bidder to be adequate to cover Contractor's overhead and profit for each separately identified item, (2) estimated quantities are not guaranteed and are solely for the purpose of comparison of Bids, and (3) final payment for all Unit Price Bid Items will be based on actual quantities, determined as provided in the Contract Documents.

Write/Type unit prices and bid prices, as clearly as possible, in number format.

Item No.	Item Description	Estimated Quantity	Unit	Bid Unit Price	Bid Price
ERBR-STPBR-0970(6)B BRADDOCKS STORE-PEOPLES ROAD (COUNTY ROAD 200)					
BASE BID ITEMS					
Roadway Items					
S-200-A	Mobilization	1.00	LS	\$	\$
S-201-A	Clearing & Grubbing	1.00	LS	\$	\$
S-202-B	Removal of Existing Bridge	1.00	UN	\$	\$
S-203-A	Unclassified Excavation (FM)	1,533.00	CY	\$	\$
S-203-E1	Borrow Excavation (FME) (Contractor Furn.) (Cl.9)	306.00	CY	\$	\$
S-202-E	Removal of Pipe (All Sizes)	93.00	LF	\$	\$
S-304-A	Granular Material (LVM) (Class 5, Group "C")	495.00	CY	\$	\$
S-304-C	Crushed Stone Size 3/4" & Down (FM)	91.00	CY	\$	\$
S-403-A	Hot Mix Ashpalt, ST, 9.5 mm	119.00	TON	\$	\$
S-403-A	Hot Mix Ashpalt, ST, 19 mm	15.00	TON	\$	\$
S-603-PE	36" Corrugated Polyethelene Pipe	140.00	LF	\$	\$
S-606-B	Guardrail "W" Beam	225.00	LF	\$	\$
S-606-D	Guardrail Bridge End Section, Type I, Thrie Beam	4.00	EA	\$	\$
S-606-E	Guardrail, Terminal End Section	4.00	EA	\$	\$
S-607-A	Roadway Construction Surveying	1.00	EA	\$	\$
S-617-A	Right Of Way Markers, Type II	8.00	EA	\$	\$

BID SCHEDULE

Item No.	Item Description	Estimated Quantity	Unit	Bid Unit Price	Bid Price
S-618-A	Maintenance of Traffic	1.00	LS	\$	\$
S-618-B	Additional Construction Signs	0.00	SF	\$	\$
S-621-C	4" Wide Thermoplastic Edge Stripe (Cont. White) (60 Mils)	0.208	MI	\$	\$
S-621-E-1	4" Wide Thermoplastic Traffic Stripe (Cont. Yellow) (90 Mils)	1,100.00	LF	\$	\$
S-627-L	Two-Way Yellow Reflective High Performance Raised Markers	10.00	EA	\$	\$
S-630-C	Reflectorized Traffic Object Marker (Encapsulated Lens) (Type 3)	4.00	EA	\$	\$
S-630-D	Reflectorized Traffic Delineator Sign (Encapsulated Lens)	18.00	EA	\$	\$
Erosion Control Items					
901-S-212-A	Agricultural Limestone	3.00	TON	\$	\$
S-212-B	Commercial Fertilizer (13-13-13)	1.50	TON	\$	\$
S-212-F	Ammonium Nitrate	0.38	TON	\$	\$
S-214-A	Seeding	1.50	AC	\$	\$
S-215-A	Vegetative Materials for Mulch	3.00	TON	\$	\$
S-226-A	Solid Sodding	100.00	SY	\$	\$
S-233-A	Temporary Silt Fence (Type I or II) (AOS 0.15-0.84)	1,400.00	LF	\$	\$
237-A	Wattles, 20"	160.00	LF	\$	\$
Bridge Items 1 @ 31'; 1 @ 60'; 1 @ 31' Prestressed Concrete Beam Spans					
S-607-B	Bridge Constuction Surveying	1.00	LS	\$	\$
S-803-A	Test Pile	2.00	EA	\$	\$
S-803-B	Conventional Static Pile Load Test	-	EA	\$ 4000.00	\$ 0.00
S-803-E	14" Steel Piling	1,800.00	LF	\$	\$

BID SCHEDULE

Item No.	Item Description	Estimated Quantity	Unit	Bid Unit Price	Bid Price
901-S-804-A	Bridge Concrete, Class "A"	179.50	CY	\$	\$
901-S-804-C	31' Prestressed Concrete Beam Type I+2	307.50	LF	\$	\$
901-S-804-C	60' Prestressed Concrete Beam Type III	298.75	LF	\$	\$
S-805-A	Reinforcement	29,125.00	LB	\$	\$
S-813-A	Concrete Railing	244.00	LF	\$	\$
S-815-A	Loose Riprap, 300 Lb	125.00	EA	\$	\$
S-815-E	Geotextile Under Riprap, Type V, AOS <0.43	232.00	SY	\$	\$
TOTAL BASE BID					\$