

The Newton County Board of Supervisors will receive bids for a Bridge Replacement Project over the Chunky River with Approaches on 0.344 miles of Griffis Fountain Road. Proposals shall be accepted no later than 10:00 a.m. local time, Friday October 24, 2025 at the Board Room of the Newton County Courthouse located at 92 West Broad Street, Decatur, Mississippi.

For the construction of: Prestressed Concrete Beam Span Bridge 1 Span @ 40 LF, 3 Spans @ 80 LF, 1 Span @ 110 LF, 1 Span @ 80 LF, 2 Spans @ 40 LF, 28 Ft Clear Roadway.

The contract documents are on file and may be examined or purchased at the following locations:

1. Chas. N. Clark Associates, 714 Hillcrest Drive, Laurel, Mississippi, 39440
2. www.clarkengineersprojects.com

Contract Time shall be One Hundred Sixty (160) Working Days.

Pay Item No.	Description	Approx. Quantity	Unit
Roadway Items			
S-200-A	Mobilization	1.0	Lump Sum
S-201-A	Clearing and Grubbing	1.0	Lump Sum
S-202-E	Removal of Pipe (All Sizes)	162.0	Lin. Ft.
S-203-A	Unclassified Excavation (F.M.)	2,411.0	Cu. Yd.
S-203-E1	Borrow Excavation (F.M.E.)(Contractor Furnished) (Class 9)	31,820.0	Cu. Yd.
S-304-D	Crushed Stone, Size 825	1,898.0	Ton
S-403-A	Hot Mix Asphalt, (ST) (9.5 mm)	274.0	Ton
S-403-A	Hot Mix Asphalt, (ST) (19 mm)	830.0	Ton
S-601-B	Class "B" Structural Concrete, Minor Structures	0.622	Cu. Yd.
S-603-C-A	18" Reinforced Concrete Pipe, Class III	32.0	Lin. Ft.
S-603-C-A	24" Reinforced Concrete Pipe, Class III	120.0	Lin. Ft.
S-603-C-A	48" Reinforced Concrete Pipe, Class III	40.0	Lin. Ft.
S-603-C-B	24" Reinforced Concrete Pipe, End Section	4.0	Each
S-603-C-B	48" Reinforced Concrete Pipe, End Section	2.0	Each
S-606-B	Guard Rail, "W" Beam	75.0	Lin. Ft.
S-606-D	Guard Rail, Bridge End Section, Thrie Beam	4.0	Each
S-606-E	Guard Rail, Terminal End Section	4.0	Each
S-607-A	Roadway Construction Surveying	1.0	Lump Sum
S-618-A	Maintenance of Traffic	1.0	Lump Sum
S-620-C	4" Wide Cold Plastic Edge Stripe (Continuous White)	0.208	Mile
S-620-E-1	4" Wide Cold Plastic Traffic Stripe (Continuous Yellow)	1,100.0	Lin. Ft.
S-621-C	4" Wide Thermoplastic Edge Stripe (Continuous White) (90 Mils)	0.465	Mile
S-621-E-1	4" Wide Thermoplastic Traffic Stripe (Continuous Yellow) (90 Mils)	2,530.0	Lin. Ft.
S-621-H-1	Thermoplastic Legend (White)(120 Mils)	150.0	Lin. Ft.
S-627-J	Two-Way Clear Reflective High Performance Raised Markers	14.0	Each

Pay Item No.	Description	Approx. Quantity	Unit
S-627-L	Two-Way Yellow Reflective High Performance Raised Markers	47.0	Each
S-630-A	Reflectorized Traffic Warning Sign (Encapsulated Lens)	6.0	Each
S-630-B	Reflectorized Traffic Regulatory Sign (Encapsulated Lens)	1.0	Each
S-630-C	Reflectorized Traffic Object Marker (Encapsulated Lens)(Type 3)	4.0	Each
630-F	Delineators, Guard Rail Bolt-On, (White Double Sided)	22.0	Each
S-815-E	Geotextile Under Bridge End Treatment, Type V, (AOS 0.21 - 0.43)	172.0	Sq. Yd.
Erosion Control Items			
S-212-A	Agricultural Limestone	10.0	Ton
S-212-B	Commercial Fertilizer (13:13:13)	4.77	Ton
S-214-A	Seeding	4.77	Acre
S-215-A	Vegetative Materials for Mulch	10.0	Ton
226-A	Temporary Grassing	4.77	Acre
S-226-A	Solid Sodding	200.0	Sq. Yd.
229-A	Erosion Mat	620.0	Sq. Yd.
S-229-A	Portland Cement Concrete Paved Ditch	14.0	Cu. Yd.
S-233-A	Temporary Silt Fence (Type II)(AOS - 0.15 - 0.84)	3,932.0	Lin. Ft.
237-A	Wattles, 12"	400.0	Lin. Ft.
Bridge Items			
S-803-A	Test Pile	2.0	Each
S-803-C	14" Steel Piling	4,365.0	Lin. Ft.
S-803-F	18" Preformed Pile Holes	2,614.0	Lin. Ft.
S-804-A	Bridge Concrete, Class "A"	640.0	Cu. Yd.
S-804-C	40' Prestressed Concrete Beam Type 1 + 2	596.25	Lin. Ft.
S-804-C	80' Prestressed Concrete Beam Type III	1,595.00	Lin. Ft.
S-804-C	110' Prestressed Concrete Beam Type IV	548.75	Lin. Ft.
S-805-A	Reinforcement	102,604.0	Lbs.
S-813-A	Concrete Railing	1,100.0	Lin. Ft.
S-815-A	Loose Riprap (300 Lb.)	880.0	Ton
S-815-E	Geotextile Under Riprap, Type V, (AOS 0.21 - 0.43)	1,712.0	Sq. Yd.