

Section 901

ADVERTISEMENT

Lincoln County, Mississippi
Site A: Mt. Olive Road, Lincoln County, Mississippi
Site B: East Lexie Road, Walthall County, Mississippi
Bridge Replacements

MDOT Project No. CHBP-0043-00(023) 108131/701000 & CHBP-0074-00(026) 108131/702000
State Aid Project No. STP/BR-0043(31)B and STP/BR-0074(26)B

The Board of Supervisors of Lincoln County, Mississippi will receive bids for the construction of the Site A: Mt. Olive Road, Lincoln County, Mississippi and Site B: East Lexie Road, Walthall County, Mississippi Bridge Replacement Project, MDOT Project No. CHBP-0043-00(023) 108131/701000 & CHBP-0074-00(026) 108131/702000 and State Aid Project No. STP/BR-0043(31)B and STP/BR-0074(26)B, no later than 10:00 A.M., Local Time, September 28, 2020, at the Lincoln County Board Office located at 301 South First Street, Brookhaven, Mississippi 39601. All bids so received will be publicly opened and read aloud.

The work shall consist essentially of the following items:

Precast and/or prestressed concrete beam span bridges and approaches, and other related items of work required to complete the project as shown and specified in the Contract Documents.

The above general outline of features of the work does not in any way limit the responsibility of the contractor to perform all work and furnish all plant, labor, equipment and materials required by the specifications and the drawings referred to therein.

The attention of bidders is directed to the Contract Provisions governing selection and employment of labor. Minimum wage rates for Federal-Aid projects have been predetermined by the Secretary of Labor and are subject to Public Law 87-581 Work Hours Act of 1962, as set forth in the Contract Provisions.

The Board of Supervisors of Lincoln County hereby notifies all Bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, disadvantaged and women's business enterprises will be afforded the full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

The award of this contract will be contingent upon the Contractor satisfying the DBE/WBE requirements.

The contract Documents are on file and may be examined at the following locations:

1. Board of Supervisors Office, 301 South First Street, Brookhaven, MS 39602, 601-835-3412
2. Dungan Engineering, PA, 120 East Chickasaw Street, Brookhaven, MS 39602, 601-823-7026

All documents required for bidding purposes may be obtained from Dungan Engineering, PA, 120 East Chickasaw Street, Brookhaven, MS 39602, 601-823-7026. A non-refundable deposit of \$250.00 is required at the time of request for Construction Drawings and Contract Documents.

Each bid shall be accompanied by a Cashier's check, Certified Check on a solvent bank or a Bidder's Bond issued by a Surety Company licensed to operate in the State of Mississippi, in the amount of five percent (5%) of the total bid price, payable to the Lincoln County Board of Supervisors as bid security. Bidders shall also submit a current financial statement, if requested by the County. The successful bidder will be required to furnish a Performance Bond and a Payment bond each in the amount of one hundred percent (100%) of the contract amount. NO STRIPPED PROPOSALS WILL BE ACCEPTED.

The proposal and contract documents in its entirety shall be submitted in a sealed envelope and deposited with the Chancery Clerk, 301 South First Street, Brookhaven, MS 39602 prior to the hour and date above designated.

Bidders choosing to submit electronically are required to contact the Lincoln County Board of Supervisors at 601-835-3412 for information regarding electronic bidding requirements.

Work to be performed shall be in accordance with the “Mississippi Standard Specifications for State Aid Road and Bridge Construction, 2004 Edition”, together with all amendments and/or special provisions and/or addenda to the standards duly approved and adopted, unless otherwise noted in these specifications.

The attention of Bidders is directed to the provisions of Section S-102 pertaining to bidding requirements and conditions.

THE BOARD OF SUPERVISORS, LINCOLN
COUNTY, MISSISSIPPI

BY Eddie Brown
President
Board of Supervisors, Lincoln County

Publish in Clarion-Ledger:
(Due by Friday, August 14, 2020 at 9:00am)

Tuesday, August 18, 2020

Tuesday, August 25, 2020

SECTION 902
PROPOSAL SHEET 2 - A

PROJECT NO. STP/BR-0043(31)B STP/BR-0074(26)B
LINCOLN and WATHALL COUNTIES, MISSISSIPPI

For the construction of: BRIDGES AND APPROACHES on SITE "A", 0.242 mile(s) of county road known as Mt. Olive Road in Lincoln County, Mississippi, under MDOT Project No. CHBP-0043-00(023) 108131/701000; AND SITE "B", 0.178 Mile(s) of county road known as East Lexie Road in Walthall County, Mississippi under MDOT Project No. CHBP-0043-00(026) 108131/702000;

I (We) agree to complete the entire project within 180 Working Days.

*** SPECIAL NOTICE TO BIDDERS ***

BIDS WILL NOT BE CONSIDERED UNLESS BOTH UNIT PRICES AND ITEM TOTALS ARE ENTERED.

SITE "A": MT. OLIVE ROAD

REF. NO.	PAY ITEM NO.	DESCRIPTION	APPROX. QUANTITY	UNIT	UNIT PRICE		ITEM TOTAL	
					DOLLARS	CENTS	DOLLARS	CENTS
		<u>ROADWAY ITEMS</u>						
1	S-200-A	Mobilization	1	LS	XXXXX	XXXXX		
2	S-201-A	Clearing and Grubbing	1	LS	XXXXX	XXXXX		
3	S-202-B	Removal of Bridge@ Sta. 14+02.32	1	UNIT				
4	S-203-A	Unclassified Excavation (FM)	4,010	CY				
5	S-203-E1	Borrow Excavation (F.M.E.) (Contractor Furnished) (Class 7)	3,613	CY				
6	S-304-A	Granular Material (LVM), (Class 4, Group B)	1,847	CY				
7	S-403-A	Hot Mix Asphalt, (ST) (12.5mm)	267	TON				
8	S-403-A	Hot Mix Asphalt, (ST) (25mm)	584	TON				
9	S-408-A	Asphalt for Prime Coat	929	GAL				
10	S-603-C-A	24" Reinforced Concrete Pipe, Class III	40	LF				
11	S-606-B	Guard Rail, W-Beam	175	LF				
12	S-606-D	Guard Rail, Bridge End Section, Type I Thrie-Beam	4	EA				
13	S-606-E	Guard Rail, Terminal End Section	4	EA				
14	S-617-A	Right-of-Way Markers (Type II)	17	EA				
15	S-618-A	Maintenance of Traffic	1	LS	XXXXX	XXXXX		
16	S-618-B	Additional Construction Signs	0	SF	\$ 10.00			\$0.00

SECTION 902
PROPOSAL SHEET 2 - B

PROJECT NO.STP/BR-0043(31)B STP/BR-0074(26)B
LINCOLN and WATHALL COUNTIES, MISSISSIPPI

REF. NO.	PAY ITEM NO.	DESCRIPTION	APPROX. QUANTITY	UNIT	UNIT PRICE		ITEM TOTAL	
					DOLLARS	CENTS	DOLLARS	CENTS
17	S-621-C	4" Wide Thermoplastic Edge Stripe (Continuous White) (60 Mils)	0.485	MI				
18	S-621-E-1	4" Wide Thermoplastic Traffic Stripe (Continuous Yellow) (90 Mils)	2,563	LF				
19	S-627-L	Two-Way Yellow Reflective High Performance Raised Markers	25	EA				
20	S-630-C	Reflectorized Traffic Object Marker (Encapsulated Lens) (Type 3)	4	EA				
SUBTOTAL SITE "A" ROADWAY ITEMS								
		<u>EROSION CONTROL ITEMS</u>						
21	S-212-B	Commerical Fertilizer (13-13-13)	3.3	TON				
22	S-214-A	Seeding	3.3	AC				
23	S-215-A	Vegetative Materials for Mulch	6.6	TON				
24	S-226-A	Solid Sodding	200	SY				
25	S-233-A	Temporary Silt Fence (Type II) (A.O.S 0.15-0.84)	2900	LF				
26	S-815-A	Loose Riprap, 200 lb.	100	TON				
27	S-815-E	Geotextile Under Loose Riprap, Type V, AOS 0.21-0.43	200	SY				
28	229-A	Erosion Mat	1,000	SY				
29	237-A	Wattles, 20 Inch	500	LF				
SUBTOTAL SITE "A" EROSION ITEMS								
		<u>BRIDGE ITEMS</u>						
ALTERNATE NO.1 (CROSS OUT ALTERNATE NOT BID)								
30	S-803-A	Test Pile	2	EA				
31	S-803-B	Convential Static Pile Load Test	0	EA	\$	4,000.00		\$0.00
32	S-803-C	14" Prestressed Concrete Piling	1,270	LF				
33	S-806-A	40' Precast Concrete Slab Unit, 3'-6" Interior	36	EA				
34	S-806-C	40' Precast Concrete Slab Unit, 3'-6" Exterior	12	EA				
35	S-806-G	Precast Concrete Barrier Rail	480	LF				
36	S-806-I	31.17' Precast Concrete Cap, Intermediate Unit, Concrete Pile	5	EA				

SECTION 902
PROPOSAL SHEET 2 - C

PROJECT NO.STP/BR-0043(31)B STP/BR-0074(26)B
LINCOLN and WATHALL COUNTIES, MISSISSIPPI

REF. NO.	PAY ITEM NO.	DESCRIPTION	APPROX. QUANTITY	UNIT	UNIT PRICE		ITEM TOTAL	
					DOLLARS	CENTS	DOLLARS	CENTS
37	S-806-J	31.17' Precast Concrete Cap, End Unit, Concrete Pile	2	EA				
38	S-806-M	9.17' Precast Concrete Wing	4	EA				
39	S-815-A	Loose Riprap, 300 lb.	238	TON				
40	S-815-E	Geotextile Under Loose Riprap, Type V, AOS 0.21-0.43	447	SY				
SUBTOTAL SITE "A" ALTERNATE NO. 1 BRIDGE ITEMS								
ALTERNATE NO.2 (CROSS OUT ALTERNATE NOT BID)								
41	S-803-A	Test Pile	2	EA				
42	S-803-B	Convential Static Pile Load Test	0	EA	\$	4,000.00		\$0.00
43	S-803-C	16" Prestressed Concrete Piling	1,550	LF				
44	901-S-804-A	Bridge Concrete, Class "A"	254.43	CY				
45	901-S-804-C	40' Prestressed Concrete Beam	1,192.50	LF				
46	S-805-A	Reinforcement	46,869.00	LB				
47	S-813-A	Concrete Railing	480.00	LF				
48	S-815-A	Loose Riprap, 300 lb.	140.00	TON				
49	S-815-E	Geotextile Under Loose Riprap, Type V, AOS 0.21-0.43	382.00	SY				
SUBTOTAL SITE "A" ALTERNATE NO. 2 BRIDGE ITEMS								
SUBTOTAL SITE "A" BRIDGE ITEMS								
SITE "A" TOTAL								

SECTION 902
PROPOSAL SHEET 2 - D

PROJECT NO.STP/BR-0043(31)B STP/BR-0074(26)B
LINCOLN and WATHALL COUNTIES, MISSISSIPPI

REF. NO.	PAY ITEM NO.	DESCRIPTION	APPROX. QUANTITY	UNIT	UNIT PRICE		ITEM TOTAL	
					DOLLARS	CENTS	DOLLARS	CENTS
SITE "B": EAST LEXIE ROAD								
		<u>ROADWAY ITEMS</u>						
50	S-200-A	Mobilization	1	LS	XXXXX	XXXXX		
51	S-201-A	Clearing and Grubbing	1	LS	XXXXX	XXXXX		
52	S-202-B	Removal of Bridge @ Sta. 53+65	1	UNIT				
53	S-203-A	Unclassified Excavation (FM)	2063	CY				
54	S-203-E	Borrow Excavation (Contractor Furnished, LVM, Class 9)	3475	CY				
55	S-203-H	Excess Excavation (LVM)	1497	CY				
56	S-304-A	Granular Material (LVM), (Class 4, Group B)	1245	CY				
57	S-403-A	Hot Mix Asphalt, (ST) (25 mm)	410.8	TON				
58	S-403-A	Hot Mix Asphalt, (ST) (12.5 mm)	255.4	TON				
59	S-408-A	Asphalt for Prime Coat (EA-1)	494.5	GAL				
60	S-606-B	Guard Rail, W-Beam	918.4	LF				
61	S-606-D	Guard Rail, Bridge End Section, Type I Thrie-Beam	4	EA				
62	S-606-E	Guard Rail, Terminal End Section	4	EA				
63	S-618-A	Maintenance of Traffic	1	LS	XXXXX	XXXXX		
64	S-618-B	Additional Construction Signs	0	SF				
65	S-620-C	4" Wide Cold Plastic Edge Stripe (Continuous White)	0.140	MI				
66	S-620-E-1	4" Wide Cold Plastic Traffic Stripe (Continuous Yellow)	740	LF				
67	S-621-C	4" Wide Thermoplastic Edge Stripe (Continuous White) (60 Mils)	0.216	MI				
68	S-621-E-1	4" Wide Thermoplastic Traffic Stripe (Continuous Yellow) (90 Mils)	1140	LF				
69	S-630-C	Reflectorized Traffic Object Markers (Encapsulated Lens)(Type 3)	4	EA				
SUBTOTAL SITE "B" ROADWAY ITEMS								
		<u>EROSION CONTROL ITEMS</u>						
70	901-S-212-A	Agricultural Limestone	1.8	TON				

SECTION 902
PROPOSAL SHEET 2 - E

PROJECT NO.STP/BR-0043(31)B STP/BR-0074(26)B
LINCOLN and WATHALL COUNTIES, MISSISSIPPI

REF. NO.	PAY ITEM NO.	DESCRIPTION	APPROX. QUANTITY	UNIT	UNIT PRICE		ITEM TOTAL	
					DOLLARS	CENTS	DOLLARS	CENTS
71	S-212-B	Commerical Fertilizer (13-13-13)	0.9	TON				
72	S-214-A	Seeding	0.9	AC				
73	S-215-A	Vegetative Materials for Mulch	1.8	TON				
74	S-233-A	Temporary Silt Fence (Type II) (AOS 0.15-0.84)	2040	LF				
75	237-A	Wattles, 20 Inches	300	LF				
SUBTOTAL SITE "B" EROSION ITEMS								
		BRIDGE ITEMS						
76	S-803-A	Test Pile	3	EA				
77	S-803-B	Conventional Static Pile Load Test	0	EA	\$ 4,000.00			\$0.00
78	S-803-C	14" Prestressed Concrete Piling	1100	LF				
79	S-803-C	16" Prestressed Concrete Piling	2720	LF				
80	S-803-F	18" Pre-Formed Pile Holes	630	LF				
81	901-S-804-A	Bridge Concrete, Class "A"	408.46	CY				
82	901-S-804-A	Bridge Concrete, Class "B"	13.2	CY				
83	901-S-804-C	110' Prestressed Concrete Beam, Type IV	548.75	LF				
84	901-S-804-C	40' Prestressed Concrete Beam, Type I+2	993.75	LF				
85	901-S-804-C	60' Prestressed Concrete Beam, Type III	298.75	LF				
86	S-805-A	Reinforcement	76182	LB				
87	S-813-A	Concrete Railing	738.84	LF				
88	S-815-A	Loose Riprap, 300 lb.	794	TON				
89	S-815-E	Geotextile Fabric Under Riprap, (Type V) AOS 0.21-0.43	1,418.00	SY				
SUBTOTAL SITE "B" BRIDGE ITEMS								
SITE "B" TOTAL								
PROJECT TOTAL BID (SITES "A" AND "B")								