



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County	Amite
Project No.	LSBP-03(26)
Road Name.	McDowell Lane

BIDS RECEIVED: FRIDAY, OCTOBER 24, 2025 AT 10:00 AM IN THE BOARDROOM AT LIBERTY, MS

Project Description: 0.132 miles of BRIDGE and APPROACHES

ROADWAY ITEMS:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF PRECAST BRIDGE AT STA. 9+82.00 (39' RT.)	1.000	UN
REMOVAL OF PIPE (ALL SIZES)	80.000	LF
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9)	1,525.000	CY
GRANULAR MATERIAL (LVM), (CLASS 5 , GROUP C)	1,227.000	CY
CRUSHED STONE SIZE 610, (FM)	32.000	CY
18 " REINFORCED CONCRETE PIPE, CLASS III	80.000	LF
18 " REINFORCED CONCRETE PIPE, END SECTION	2.000	EA
RIGHT-OF-WAY MARKERS (TYPE II)	13.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	1.640	TON
COMMERCIAL FERTILIZER (13-13-13)	0.330	TON
SEEDING	0.820	AC
VEGETATIVE MATERIALS FOR MULCH	2.460	TON
EXCELSIOR BLANKET	400.000	SY
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15 - 0.84)	1,500.000	LF
WATTLES, 20"	300.000	LF

BRIDGE ITEMS:

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14 " PRESTRESSED CONCRETE PILING	660.000	LF
18 " PRE-FORMED PILE HOLES	200.000	LF
19 ' PRECAST CONCRETE SLAB UNIT, 3.5 ' INTERIOR	12.000	EA
31 ' PRECAST CONCRETE SLAB UNIT, 3.5 ' INTERIOR	6.000	EA
19 ' PRECAST CONCRETE SLAB UNIT, CURB	4.000	EA
31 ' PRECAST CONCRETE SLAB UNIT, CURB	2.000	EA
BEAM TYPE RAILING WITH CONCRETE POSTS	138.000	LF
29 ' PRECAST CONCRETE CAP, INTERMEDIATE UNIT, CONCRETE PILE,	2.000	EA

29 ' PRECAST CONCRETE CAP, END UNIT, CONCRETE PILE,	2.000	EA
7.5' PRECAST CONCRETE WING	4.000	EA
LOOSE RIPRAP, 300 LB.	98.000	TON
GEOTEXTILE UNDER RIPRAP, (TYPE V), (AOS <0.43) Non-Woven	275.000	SY