



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County Bolivar

Project No. LSBP-06(25)

Road Name. Martin Luther King Drive

BIDS RECEIVED: 10 am at the Bolivar County Annex Building on April 1, 2026

Project Description: 0.041 miles of BOX CULVERT and APPROACHES

ROADWAY ITEMS:

	QUANTITY	UNIT
MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF PRECAST BRIDGE (STA. 3+64.43)	1.000	UN
REMOVAL OF COMBINATION CURB & GUTTER	27.000	LF
UNCLASSIFIED EXCAVATION (FM)	124.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9)	511.000	CY
STRUCTURE EXCAVATION	433.000	CY
TEMPORARY STREAM DIVERSION	1.000	EA
CRUSHED STONE, SIZE #57	111.000	TON
CRUSHED STONE, SIZE #610	352.000	TON
CLASS BB STRUCTURAL CONCRETE	113.790	CY
CLASS B STRUCTURAL CONCRETE, MINOR STRUCTURES	0.620	CY
REINFORCING STEEL	21,941.000	LB
18" REINFORCED CONCRETE PIPE, CLASS III	152.000	LF
18" REINFORCED CONCRETE PIPE, END SECTION	3.000	EA
18" BRANCH CONNECTION (R.C.P. TO WINGWALL OF BOX)	4.000	EA
GRATINGS	250.000	LB
RIGHT-OF-WAY MARKERS (TYPE II)	10.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
HOT MIX ASPHALT, ST 12.5mm	66.000	TON
CONCRETE SIDEWALK	98.000	SY

EROSION CONTROL ITEMS:

	QUANTITY	UNIT
COMMERCIAL FERTILIZER (13:13:13)	0.090	TON
SEEDING	0.230	AC
VEGETATIVE MATERIALS FOR MULCH	0.470	TON
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	605.000	LF
WATTLES, 20"	120.000	LF
LOOSE RIPRAP, 300 LB.	26.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, AOS <0.43	41.000	SY