



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County	Bolivar
Project No.	LSBP-06(26)
Road Name.	Lee Street

BIDS RECEIVED: TUESDAY, NOVEMBER 25, 2025 AT 10:00 AM IN THE ANNEX BUILDING AT CLEVELAND, MS

Project Description: 0.134 miles of BOX BRIDGE and APPROACHES

ROADWAY ITEMS:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF PRECAST BRIDGE @ STA 3+58.22	1.000	UN
REMOVAL OF PIPE (ALL SIZES)	20.000	LF
UNCLASSIFIED EXCAVATION (FM)	389.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9)	744.000	CY
STRUCTURE EXCAVATION	1,307.000	CY
TEMPORARY STREAM DIVERSION	1.000	EA
CRUSHED STONE, SIZE #57	348.000	TON
CRUSHED STONE, SIZE #610	1,040.000	TON
HOT MIX ASPHALT, ST 12.5mm	223.000	TON
CLASS B STRUCTURAL CONCRETE, MINOR STRUCTURES	0.320	CY
18" REINFORCED CONCRETE PIPE, CLASS III	144.000	LF
24" REINFORCED CONCRETE PIPE, CLASS III	48.000	LF
18" REINFORCED CONCRETE PIPE, END SECTION	2.000	EA
24" REINFORCED CONCRETE PIPE, END SECTION	1.000	EA
18" BRANCH CONNECTION (R.C.P. TO WINGWALL OF BOX)	3.000	EA
24" BRANCH CONNECTION (R.C.P. TO WINGWALL OF BOX)	1.000	EA
RIGHT-OF-WAY MARKERS (TYPE II)	14.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF

EROSION CONTROL ITEMS:

COMMERCIAL FERTILIZER (13:13:13)	0.213	TON
SEEDING	0.567	AC
VEGETATIVE MATERIALS FOR MULCH	1.134	TON
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	1,817.000	LF
WATTLES, 20"	120.000	LF
LOOSE RIPRAP, 300 LB.	50.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, AOS <0.43, NON-WOVEN	84.000	SY

BOX BRIDGE ITEMS:

BOX BRIDGE CONCRETE, CLASS BB	322.120	CY
REINFORCEMENT	61,405.900	LB

