



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County	Bolivar
Project No.	LSBP-06(27)
Road Name.	Bond-Busby

BIDS RECEIVED: THURSDAY, JULY 31, 2025 AT 10:00 AM IN THE ANNEX BUILDING AT CLEVELAND, MS

Project Description: 0.098 miles of BRIDGE and APPROACHES

ROADWAY ITEMS:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF PRECAST BRIDGE @ STA. 4+76.17	1.000	UN
REMOVAL OF PIPE (ALL SIZES)	264.000	LF
UNCLASSIFIED EXCAVATION (F.M.)	915.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9)	190.000	CY
CRUSHED STONE, SIZE #610	638.000	TON
18" REINFORCED CONCRETE PIPE, CLASS III	88.000	LF
24" REINFORCED CONCRETE PIPE, CLASS III	224.000	LF
42" REINFORCED CONCRETE PIPE, CLASS III	80.000	LF
RIGHT-OF-WAY MARKERS (TYPE II)	10.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE III)	4.000	EA

EROSION CONTROL ITEMS:

COMMERCIAL FERTILIZER (13:13:13)	0.680	TON
SEEDING	1.820	AC
VEGETATIVE MATERIALS FOR MULCH	3.640	TON
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	1,202.000	LF
WATTLES, 20"	180.000	LF
LOOSE RIPRAP, 300 LB.	220.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, AOS < 0.43, NON-WOVEN	349.000	SY

BRIDGE ITEMS:

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
18" PRESTRESSED CONCRETE PILING	1,220.000	LF
24" PRE-FORMED PILE HOLES	200.000	LF
BRIDGE CONCRETE, CLASS A	77.900	CY
REINFORCEMENT	14,829.000	LB
19' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR	8.000	EA
40' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR	12.000	EA
19' PRECAST CONCRETE SLAB UNIT, 4.5' INTERIOR	4.000	EA

40' PRECAST CONCRETE SLAB UNIT, 4.5' INTERIOR	6.000	EA
19' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR	4.000	EA
40' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR	6.000	EA
PRECAST CONCRETE BARRIER RAIL	316.000	LF
LOOSE RIPRAP, 300 LB.	84.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, AOS < 0.43, NON-WOVEN	133.000	SY