



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County	<u>Bolivar</u>
Project No.	<u>LSBP-06(28)</u>
Road Name.	<u>Laughlin Road</u>

BIDS RECEIVED: WEDNESDAY, SEPTEMBER 10, 2025 AT 8:00 AM IN THE BOLIVAR COUNTY ANNEX BUILDING AT CLEVELAND, MS

Project Description: 0.113 miles of BRIDGE and APPROACHES

ROADWAY ITEMS:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF PRECAST BRIDGE @ STA 2+99.77	1.000	UN
REMOVAL OF PIPE (ALL SIZES)	233.000	LF
UNCLASSIFIED EXCAVATION (F.M.)	674.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9)	560.000	CY
CRUSHED STONE, SIZE #610	818.000	TON
18" REINFORCED CONCRETE PIPE, CLASS III	120.000	LF
30" REINFORCED CONCRETE PIPE, CLASS III	56.000	LF
RIGHT-OF-WAY MARKERS (TYPE II)	4.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA

EROSION CONTROL ITEMS:

COMMERCIAL FERTILIZER (13:13:13)	0.320	TON
SEEDING	0.850	AC
VEGETATIVE MATERIALS FOR MULCH	1.692	TON
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	1,203.000	LF
WATTLES, 20"	280.000	LF
LOOSE RIPRAP, 300 LB.	107.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, AOS < 0.43, NON-WOVEN	169.000	SY

BRIDGE ITEMS:

TEST PILES	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
18" PRESTRESSED CONCRETE PILING	800.000	LF
24" PRE-FORMED PILE HOLES	200.000	LF
BRIDGE CONCRETE, CLASS A	49.400	CY
REINFORCEMENT	9,258.000	LB
19' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR	8.000	EA
19' PRECAST CONCRETE SLAB UNIT, 4.5' INTERIOR	4.000	EA
40' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR	4.000	EA
40' PRECAST CONCRETE SLAB UNIT, 4.5' INTERIOR	2.000	EA

19' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR	4.000	EA
40' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR	2.000	EA
PRECAST CONCRETE BARRIER RAIL	156.000	LF
LOOSE RIPRAP, 300 LB.	86.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, AOS < 0.43, NON-WOVEN	136.000	SY