



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)

AND

COUNTY BOARD OF SUPERVISORS

County Calhoun

Project No. LSBP-07(32)

Road Name. COUNTY ROAD 453

BIDS RECEIVED: MONDAY, JULY 7, 2025 AT 10:00 AM IN THE COURTHOUSE AT PITTSBORO, MS

Project Description: 0.08 miles of BRIDGE & APPROACHES

Roadway Items:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF BRIDGE @ STA. 2+04	1.000	UN
REMOVAL OF PIPE (ALL SIZES)	24.000	LF
UNCLASSIFIED EXCAVATION (FM)	721.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9)	338.000	CY
GRANULAR MATERIAL, (CLASS 4, GROUP "B")	429.000	TON
18" CORRUGATED HIGH DENSITY POLYETHYLENE DRAINAGE PIPE	80.000	LF
ROADWAY CONSTRUCTION SURVEYING	1.000	LS
RIGHT-OF-WAY MARKERS (TYPE II)	7.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	1.260	TON
COMMERCIAL FERTILIZER (13:13:13)	0.630	TON
AMMONIUM NITRATE	0.060	TON
SEEDING	0.630	AC
VEGETATIVE MATERIALS FOR MULCH	1.890	TON
EXCELSIOR BLANKET	515.000	SY
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	200.000	LF
WATTLES, 12"	300.000	LF

BRIDGE ITEMS:

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14" PRESTRESSED CONCRETE PILING	520.000	LF
18" PRE-FORMED PILE HOLES	295.000	LF
19' PRECAST CONCRETE SLAB UNIT, 3.5 ' INTERIOR, 30 DEG SKEW, LT. FWD	12.000	EA
40' PRECAST CONCRETE SLAB UNIT, 3.5 ' INTERIOR, 30 DEG SKEW, LT. FWD	6.000	EA
19' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR, 30 DEG SKEW, LT. FWD	4.000	EA
40' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR, 30 DEG SKEW, LT. FWD	2.000	EA
PRECAST CONCRETE BARRIER RAIL	156.000	LF
36.17' PRECAST CONCRETE CAP, INTERMEDIATE UNIT, CONCRETE PILE, 30 DEG SKEW, LT. FWD.	2.000	EA
36' PRECAST CONCRETE CAP, END UNIT, CONCRETE PILE, 30 DEG SKEW, LT. FWD.	2.000	EA

11.33' PRECAST CONCRETE WING	4.000	EA
LOOSE RIPRAP, 300 LB.	294.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, NON-WOVEN, AOS <0.43	551.000	SY