



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)

AND

COUNTY BOARD OF SUPERVISORS

County Carroll

Project No. LSBP-08(47)

Road Name. COUNTY ROAD 150

BIDS RECEIVED: MONDAY, JUNE 30, 2025 AT 10:00 AM IN THE COURTHOUSE AT VAIDEN, MS

Project Description: 0.105 miles of BOX CULVERT & APPROACHES

Roadway Items:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF BRIDGE @ STA. 2+63	1.000	UN
REMOVAL OF CONCRETE DRIVEWAY	30.000	SY
UNCLASSIFIED EXCAVATION (FM)	3,147.000	CY
CHANNEL EXCAVATION (FM)	190.000	CY
EXCESS EXCAVATION (FM)	301.000	CY
STRUCTURE EXCAVATION	850.000	CY
TEMPORARY STREAM DIVERSION	1.000	EA
GRANULAR MATERIAL, (CLASS 4, GROUP "B")	680.000	TON
CRUSHED STONE, SIZE 57	270.000	TON
CLASS "B" STRUCTURAL CONCRETE	205.570	CY
REINFORCING STEEL	39,644.000	LB
24" REINFORCED CONCRETE PIPE, CLASS III	40.000	LF
ROADWAY CONSTRUCTION SURVEYING	1.000	LS
RIGHT-OF-WAY MARKERS (TYPE II)	8.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	2.000	TON
COMMERCIAL FERTILIZER (13:13:13)	1.000	TON
AMMONIUM NITRATE	0.100	TON
SEEDING	1.000	AC
VEGETATIVE MATERIALS FOR MULCH	3.000	TON
EXCELSIOR BLANKET	685.000	SY
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	1,000.000	LF
WATTLES, 12"	250.000	LF
LOOSE RIPRAP, 300 LB.	455.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, NON-WOVEN AOS<0.43	1,215.000	SY