



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County	Carroll
Project No.	LSBP-08(48)
Road Name.	COUNTY ROAD 316

BIDS RECEIVED: MONDAY, AUGUST 31, 2026 AT 10:00 AM IN THE COURTHOUSE AT VAIDEN, MS

Project Description: 0.063 miles of BRIDGE REPLACEMENT

ROADWAY ITEMS:

Mobilization	1.000	LS
Clearing and Grubbing	1.000	LS
Removal of Bridge @ STA. 3+47	1.000	UN
Removal of Existing Drain Inlet @ STA 4+97	1.000	UN
Removal of Pipe (All Sizes)	107.000	LF
REMOVE AND RELAY RIPRAP	1,015.000	SY
Unclassified Excavation (FM)	1,032.000	CY
Borrow Excavation (Contractor-Furnished FME, Class 9)	81.000	CY
Granular Material, (Class 4, Group B)	392.000	TON
CRUSHED STONE, Size 610	100.000	TON
36" Corrugated Polyethylene Pipe	104.000	LF
42" Corrugated Polyethylene Pipe	88.000	LF
Roadway Construction Surveying	1.000	LS
Right-of-Way Markers (TYPE II)	8.000	EA
Maintenance of Traffic	1.000	LS
Additional Construction Signs	0.000	SF
Reflectorized Traffic Object Marker (Encapsulated Lens) (Type 3)	4.000	EA

EROSION CONTROL ITEMS:

Agricultural Limestone	0.920	TON
Commercial Fertilizer (13:13:13)	0.460	TON
Ammonium Nitrate	0.050	TON
Seeding	0.460	AC
Vegetative Materials for Mulch	1.380	TON
Excelsior Blanket	295.000	SY
Temporary Silt Fence (Type II) (AOS 0.15-0.84)	400.000	LF
Wattles, 12"	200.000	LF
Loose Riprap, 300 LB.	150.000	TON
Geotextile under RIPRAP, Type V, NON-WOVEN, AOS <0.43	285.000	SY

BRIDGE ITEMS:

Test Pile, 18" PRESTRESSED CONCRETE PILING	2.000	EA
Conventional Static Pile Load Test	0.000	EA
18" Prestressed Concrete Piling	600.000	LF

24" Preformed Pile Hole	300.000	LF
Bridge Concrete, Class "AA"	45.180	CY
Reinforcement	8,024.000	LB
19' Precast Concrete Slab Unit, 3.5' Interior	12.000	EA
31' Precast Concrete Slab Unit, 3.5' Interior	6.000	EA
19' Precast Concrete Slab Unit, 3.5' Exterior	4.000	EA
31' Precast Concrete Slab Unit, 3.5' Exterior	2.000	EA
Precast Concrete Barrier Rail	138.000	LF
Loose Riprap, 300 LB.	375.000	TON
Geotextile under RIPRAP, Type V, NON-WOVEN, AOS <0.43	700.000	SY