



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)

AND

COUNTY BOARD OF SUPERVISORS

County Chickasaw
Project No. LSBP-09(14)
Road Name. Dulaney Street

BIDS RECEIVED: MONDAY, OCTOBER 6, 2025 AT 10:00 AM IN THE BOARDROOM AT OKOLONA, MS
Project Description: 0.056 miles of BRIDGE & APPROACHES

Roadway Items:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF EXISTING BRIDGE	1.000	UN
UNCLASSIFIED EXCAVATION (FM)	36.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9)	270.000	CY
EXCESS EXCAVATION (FM)	95.000	CY
GEOTEXTILE FABRIC STABILIZATION (TYPE V) (AOS <0.43)	834.000	SY
CRUSHED STONE SIZE 3/4" & DOWN, (FM)	137.000	CY
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	0.400	TON
COMMERCIAL FERTILIZER (13-13-13)	0.200	TON
SEEDING	0.200	AC
VEGETATIVE MATERIALS FOR MULCH	0.600	TON
SOLID SODDING	100.000	SY
TEMPORARY SILT FENCE (TYPE I OR II) (AOS 0.15-0.84)	800.000	LF
WATTLES, 20" DIAMETER	80.000	LF

BRIDGE ITEMS:

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
HP 12 X 53 STEEL PILING	400.000	LF
16 " PRE-FORMED PILE HOLES	240.000	LF
BRIDGE CONCRETE, CLASS A	3.000	CY
REINFORCEMENT	50.000	LB
19 ' PRECAST CONCRETE SLAB UNIT, 3.5 ' INTERIOR	6.000	EA
31 ' PRECAST CONCRETE SLAB UNIT, 3.5 ' INTERIOR	6.000	EA
19 ' PRECAST CONCRETE SLAB UNIT, 3.5 ' EXTERIOR	2.000	EA
31 ' PRECAST CONCRETE SLAB UNIT, 3.5 ' EXTERIOR	2.000	EA
PRECAST CONCRETE BARRIER RAIL	100.000	LF
31 ' PRECAST CONCRETE CAP, INTERMEDIATE UNIT, STEEL PILE,	1.000	EA
31 ' PRECAST CONCRETE CAP, END UNIT, STEEL PILE,	2.000	EA
9.25' PRECAST CONCRETE WING	4.000	EA

LOOSE RIPRAP, 300 LB.	438.000	TON
GEOTEXTILE FABRIC UNDER RIPRAP, TYPE V, AOS <0.43	450.000	SY