



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County Coahoma

Project No. LSBP-14(11)

Road Name. OLD HIGHWAY 49 (E. TALLAHATCHIE STREET)

BIDS RECEIVED: FRIDAY, AUGUST 28, 2026 AT 10:00 AM IN THE COAHOMA COUNTY COURTHOUSE AT CLARKSDALE, MS

Project Description: 0.113 miles of BRIDGE and APPROACHES

ROADWAY ITEMS:

	QUANTITY	UNIT
Mobilization	1.000	LS
Clearing and Grubbing	1.000	LS
Removal of Obstructions	1.000	LS
Removal of Precast Bridge @ STA. 15+22.00	1.000	UN
Removal of Pavement	1,074.000	SY
Removal of Pipe (All Sizes)	60.000	LF
Unclassified Excavation (FM)	860.000	CY
Borrow Excavation (Contractor-Furnished, FME, Class 9)	170.000	CY
Channel Excavation (FM)	1,603.000	CY
Crushed Stone No. 610	475.000	TON
36" Polymeric Coated Corr. Metal Pipe, 14 Gauge, 2-2/3" Corrugation	40.000	LF
Right of Way Markers (Type II)	2.000	EA
Maintenance of Traffic	1.000	LS
Additional Construction Signs	0.000	SF
Reflectorized Traffic Object Marker (Encapsulated Lens) (Type 3)	4.000	EA

EROSION CONTROL ITEMS:

	QUANTITY	UNIT
Agricultural Limestone	1.080	TON
Commercial Fertilizer (13:13:13)	0.540	TON
Seeding	0.540	AC
Vegetative Materials for Mulch	1.620	TON
Temporary Silt Fence (Type II) (AOS 0.15 - 0.84)	1,005.000	LF
Wattles, 20"	200.000	LF

BRIDGE ITEMS:

	QUANTITY	UNIT
Test Pile, 14" Steel	2.000	EA
Conventional Static Pile Load Test	0.000	EA
14" Steel Piling	1,930.000	LF
18" Pre-formed Pile Hole	600.000	LF
Bridge Concrete, Class AA	137.000	CY
Reinforcement	17,501.000	LB
31' Precast Concrete Slab Unit, 3.5' Interior, 30° Skew, Left Fwd.	24.000	EA
31' Precast Concrete Slab Unit, 4.5' Interior, 30° Skew, Left Fwd.	12.000	EA
31' Precast Concrete Slab Unit, 3.5' Exterior, 30° Skew, Left Fwd.	12.000	EA

Precast Concrete Barrier Rail	372.000	LF
Loose Riprap, 300 LB	520.000	TON
Geotextile under Riprap, Type V, Non-Woven, AOS < 0.43	991.000	SY