



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County Copiah
Project No. LSBP-15(21)
Road Name. W. Gallatin Street

BIDS RECEIVED: FRIDAY, MAY 8, 2026 AT 10:00 AM IN THE BOARDROOM AT HAZLEHURST, MS

Project Description: 0.147 miles of BRIDGE and APPROACHES

ROADWAY ITEMS:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF BRIDGE @ STA. 13+44	1.000	EA
REMOVAL OF EXISTING ASPHALT PAVEMENT (ALL DEPTHS)	1,545.000	SY
REMOVAL OF PIPE (ALL SIZES)	64.000	LF
UNCLASSIFIED EXCAVATION (FM)	189.000	CY
EXCESS EXCAVATION (FM)	3,017.000	CY
GRANULAR MATERIAL (L.V.M.)(CLASS 4, GROUP "B")	863.000	CY
18" REINFORCED CONCRETE PIPE, CLASS III	64.000	LF
ROADWAY CONSTRUCTION SURVEYING	1.000	LS
BRIDGE CONSTRUCTION SURVEYING	1.000	LS
RIGHT-OF-WAY MARKERS (TYPE I)	12.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA
HOT MIX ASPHALT ST, 9.5MM	180.000	TON
HOT MIX ASPHALT ST, 19MM	355.000	TON
4" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (90 MILS)	0.295	MILE
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (90 MILS)	1,558.000	LF
TWO-WAY CLEAR REFLECTIVE RAISED MARKERS	40.000	EA
TWO-WAY YELLOW REFLECTIVE RAISED MARKERS	20.000	EA

EROSION CONTROL ITEMS:

HYDROSEEDING	1.300	AC
TEMPORARY SILT FENCE (TYPE I) (AOS 0.15-0.84)	1,300.000	LF
WATTLES, 20"	220.000	LF
LOOSE RIPRAP, 100 LB.	20.000	TON

BRIDGE ITEMS:

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14 " PRESTRESSED CONCRETE PILING	1,000.000	LF
18" PRE-FORMED PILE HOLES	500.000	LF
31' PRECAST CONCRETE SLAB UNIT, 3.5 ' INTERIOR, 30 DEG SKEW, RT FWD	24.000	EA

40' PRECAST CONCRETE SLAB UNIT, 3.5 ' INTERIOR, 30 DEG SKEW, RT FWD	6.000	EA
31' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR, 30 DEG SKEW, RT FWD	8.000	EA
40' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR, 30 DEG SKEW, RT FWD	2.000	EA
PRECAST CONCRETE BARRIER RAIL	328.000	LF
36' PRECAST CONCRETE CAP, INTERMEDIATE UNIT, CONCRETE PILE,30 DEG SKEW, RT FWD.	2.000	EA
36.17' PRECAST CONCRETE CAP, INTERMEDIATE UNIT, CONCRETE PILE,30 DEG SKEW, RT FWD.	2.000	EA
36' PRECAST CONCRETE CAP, END UNIT, CONCRETE PILE, 30 DEG SKEW, RT FWD.	2.000	EA
11.33' PRECAST CONCRETE WING	4.000	EA
LOOSE RIPRAP (#300)	907.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, NON-WOVEN, AOS <0.43	1,680.000	SY