



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County	Covington
Project No.	LSBP-16(25)
Road Name.	Cotton Street

BIDS RECEIVED: TUESDAY, SEPTEMBER 2, 2025 10:00 AM IN THE BOARDROOM AT COLLINS, MS

Project Description: 0.076 miles of BRIDGE and APPROACHES

ROADWAY ITEMS:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF BRIDGE @ STA. 41+44.00	1.000	UN
UNCLASSIFIED EXCAVATION (FM)	150.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CL. 9)	1,750.000	CY
GRANULAR MATERIAL (LVM), (CL. 5, GP. "C")	770.000	CY
RIGHT-OF-WAY MARKERS (TYPE II)	4.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	0.800	TON
COMMERCIAL FERTILIZER (13-13-13)	0.800	TON
AMMONIUM NITRATE	0.160	TON
SEEDING	0.800	AC
VEGETATIVE MATERIALS FOR MULCH	0.800	TON
SOLID SODDING	200.000	SY
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	200.000	LF
WATTLES, 20"	80.000	L.F.
LOOSE RIPRAP, 200 LB.	100.000	TON

BRIDGE ITEMS:

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14 " PRESTRESSED CONCRETE PILING	980.000	LF
18 " PRE-FORMED PILE HOLES	200.000	LF
40 ' PRECAST CONCRETE SLAB UNIT, 3.5 ' INTERIOR	18.000	EA
40 ' PRECAST CONCRETE SLAB UNIT, 3.5 ' EXTERIOR	6.000	EA
PRECAST CONCRETE BARRIER RAIL	240.000	LF
31.17 ' PRECAST CONCRETE CAP, INTERMEDIATE UNIT, CONCRETE PILE	2.000	EA
31.17 ' PRECAST CONCRETE CAP, END UNIT, CONCRETE PILE	2.000	EA
9.17' PRECAST CONCRETE WING	4.000	EA
LOOSE RIPRAP, 300 LB.	235.000	TON

GEOTEXTILE UNDER RIPRAP (TYPE V) (AOS < 0.43) (NON-WOVEN)

620.000

SY