OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS

County Covington
Project No. LSBP-16(26)
Road Name. Big V Road

BIDS RECEIVED: MONDAY, JANUARY 4, 2027 AT 10:00 AM IN THE BOARDROOM AT COLLINS, MS
Project Description: 0.193 miles of BRIDGE and APPROACHES

ROADWAY ITEMS:	QUANTITY	UNIT
Mobilization	1.000	LS
Clearing and Grubbing	1.000	LS
Borrow Excavation (Contractor-Furnished FME, Class 9)	8,950.000	CY
Granular Material [LVM], (Class 5, Group C)	1,450.000	CY
15" REINFORCED CONCRETE PIPE, CLASS III	32.000	LF
Right-of-Way Markers II	17.000	EA
Maintenance of Traffic	1.000	LS
Additional Construction Signs	0.000	SF
Reflectorized Traffic Object Marker (Encapsulated Lens) (Type 3)	4.000	EA

EROSION CONTROL ITEMS:	QUANTITY	UNIT
Agricultural Limestone	0.800	TON
Commercial Fertilizer (13-13-13)	0.800	TON
Ammonium Nitrate	0.160	TON
Seeding	0.800	AC
Vegetative Materials for Mulch	0.800	TON
Solid Sodding	200.000	SY
Temporary Silt Fence (Type II) (AOS 0.15-0.84)	800.000	LF
Wattles, 20"	80.000	LF
Loose Riprap, 200 LB	100.000	TON

BRIDGE ITEMS:	QUANTITY	UNIT
Test Pile, 14", Prestressed Concrete	2.000	EA
Conventional Static Pile Load Test	0.000	EA
14” Prestressed Concrete Piling	980.000	LF
18” Preformed Pile Hole	200.000	LF
40' Precast Concrete Slab Unit, 3.5' Interior	18.000	EA
40' Precast Concrete Slab Unit, 3.5' Exterior	6.000	EA
Precast Concrete Barrier Rail	240.000	LF
31.17' Precast Concrete Cap, Intermediate Unit, Concrete Pile	2.000	EA
31.17' Precast Concrete Cap, End Unit, Concrete Pile	2.000	EA
9.17' Precast Concrete Wing	4.000	EA
Loose Riprap, 300 LB	235.000	TON
Geotextile under Riprap, Type V, (AOS < 0.43), (Non-Woven)	621.000	SY