



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County Forrest

Project No. LSBP-18(17)

Road Name. Archie Smith Road

BIDS RECEIVED: THURSDAY, SEPTEMBER 17, 2026 AT 10:00 AM IN THE BOARDROOM AT HATTIESBURG, MS

Project Description: 0.112 miles of BRIDGE and APPROACHES

ROADWAY ITEMS:

	QUANTITY	UNIT
Mobilization	1.000	LS
Clearing and Grubbing	1.000	LS
Removal of Bridge @ Sta. 99+86	1.000	UN
Removal of Asphalt Pavement (All Depths)	657.000	SY
Remove and Relay Riprap	376.000	SY
Borrow Excavation (FME) (Contractor Furnished) (Class 9)	1,802.000	CY
Granular Material LVM, (Class 6, Group "C")	657.000	CY
Guardrail, "W" Beam	75.000	LF
Guardrail, Bridge End Section, Type "I", Thrie Beam	4.000	EA
Guardrail, Terminal End Section	4.000	EA
Right-of-Way Markers (Type 1)	18.000	EA
Maintenance of Traffic	1.000	LS
Additional Construction Signs	0.000	SF
Reflectorized Traffic Object Marker (Encapsulated Lens) (Type 3)	4.000	EA

EROSION CONTROL ITEMS:

	QUANTITY	UNIT
Agricultural Limestone	1.400	TON
Commercial Fertilizer (13-13-13)	0.700	TON
Seeding	0.700	AC
Vegetative Materials for Mulch	2.100	TON
Temporary Silt Fence (Type II) (AOS 0.15-0.84)	1,000.000	LF
Wattles, 20"	500.000	LF

BRIDGE ITEMS:

	QUANTITY	UNIT
Test Pile, 14" Concrete	2.000	EA
Conventional Static Pile Load Test	0.000	EA
14" Prestressed Concrete Piling	1,350.000	LF
18" Preformed Pile Hole	150.000	LF
Bridge Concrete, Class "B"	6.060	CY
Reinforcement	724.000	LB
40' Precast Concrete Slab Unit, 3.5' Interior, 30° Skew, Rt. Fwd.	30.000	EA
40' Precast Concrete Slab Unit, 3.5' Exterior, 30° Skew, Rt. Fwd.	10.000	EA
Precast Concrete Barrier Rail	400.000	LF
36.25' Precast Concrete Cap, Intermediate Unit, Concrete Pile, 30° Skew, Rt. Fwd.	4.000	EA

36' Precast Concrete Cap, End Unit, Concrete Pile, 30° Skew, Rt. Fwd.	2.000	EA
11' Precast Concrete Wing	4.000	EA
Loose Riprap, 300 Lb.	338.000	TON
Geotextile under Riprap, Type V, Non-Woven, AOS < 0.43	703.000	SY