



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County George

Project No. LSBP 20(15)

Road Name. MOFFETT ROAD

BIDS RECEIVED: TUESDAY, SEPTEMBER 30, 2025 AT 10:00 AM IN THE BOARDROOM AT LUCEDALE, MS

Project Description: 0.086 miles of BRIDGE and APPROACHES

ROADWAY ITEMS:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF PRECAST BRIDGE AT STATION 87+35	1.000	UN
REMOVAL OF ASPHALT (ALL DEPTHS)	963.000	SY
REMOVAL OF PIPE (ALL SIZES)	40.000	LF
UNCLASSIFIED EXCAVATION (FM)	380.000	CY
BORROW EXCAVATION (CONTRACTOR FURNISHED) (LVM) (CLASS 7)	1,212.000	CY
CRUSHED STONE (SIZE 610) (LVM)	496.000	CY
RIGHT-OF-WAY MARKERS (TYPE I)	8.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) TYPE 3	4.000	EA
GEOTEXTILE FABRIC UNDER BRIDGE END TREATMENT, TYPE V, AOS <0.43 NON-WOVEN	92.000	SY

EROSION CONTROL ITEMS:

TOPSOIL FOR SLOPE TREATMENT (CONTRACTOR FURNISHED) (LVM)	260.000	CY
AGRICULTURAL LIMESTONE	0.800	TON
COMMERCIAL FERTILIZER (13-13-13)	0.400	TON
SEEDING	0.400	AC
VEGETATIVE MATERIALS FOR MULCH	1.200	TON
SOLID SODDING	1,620.000	SY
EXCELSIOR BLANKET	1,620.000	SY
Wattles, 20"	980.000	LF

BRIDGE ITEMS:

TEST PILES	2.000	EA
14 " PRESTRESSED CONCRETE PILING	520.000	LF
18" PRE-FORMED PILE HOLE	385.000	LF
31 ' PRECAST CONCRETE SLAB UNIT, 3.5 ' INTERIOR	18.000	EA
31 ' PRECAST CONCRETE SLAB UNIT, CURB	6.000	EA
BEAM TYPE RAILING WITH CONCRETE POSTS	186.000	LF
29.0 ' PRECAST CONCRETE CAP, INTERMEDIATE UNIT, CONC. PILE,	2.000	EA
29.0 ' PRECAST CONCRETE CAP, END UNIT, CONC. PILE,	2.000	EA
7.5' PRECAST CONCRETE WING	4.000	EA
LOOSE RIPRAP, 200 LB.	180.000	SY
GEOTEXTILE UNDER RIPRAP, TYPE V, AOS <0.43 NON-WOVEN	333.000	SY