



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)

AND

COUNTY BOARD OF SUPERVISORS

County Greene

Project No. LSBP-21(14)

Road Name. BEXLEY ROAD

BIDS RECEIVED: WEDNESDAY, OCTOBER 1, 2025 AT 10:00 AM IN THE BOARDROOM AT LEAKESVILLE, MS

Project Description: 0.131 miles of BOX BRIDGE & APPROACHES

Roadway Items:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF BRIDGE AT STATION 14+51	1.000	UN
REMOVAL OF PAVEMENT	1,450.000	SY
UNCLASSIFIED EXCAVATION (FM)	1,290.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 7)	1,320.000	CY
STRUCTURE EXCAVATION	700.000	CY
GEOGRID, TYPE III	900.000	SY
TEMPORARY STREAM DIVERSION	1.000	EA
GRANULAR MATERIAL (LVM), (CLASS 9, GROUP B)	1,475.000	CY
CRUSHED STONE, 610	200.000	TON
SIZE II STABILIZER AGGREGATE, COARSE	250.000	CY
CLASS B STRUCTURAL CONCRETE, MINOR STRUCTURES	0.252	CY
18" REINFORCED CONCRETE PIPE, CLASS III	56.000	LF
18" REINFORCED CONCRETE PIPE, END SECTION	4.000	EA
RIGHT-OF-WAY MARKERS (TYPE I)	11.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	2.400	TON
COMMERCIAL FERTILIZER (13-13-13)	1.200	TON
SEEDING	1.200	AC
VEGETATIVE MATERIALS FOR MULCH	3.600	TON
SOLID SODDING	200.000	SY
EXCELSIOR BLANKET	450.000	SY
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	1,500.000	LF
WATTLES, 20"	300.000	LF
REMOVE AND RESET RIPRAP	100.000	CY
LOOSE RIPRAP, 200 LB.	200.000	TON
GEOTEXTILE UNDER RIPRAP NON-WOVEN, TYPE V, AOS < 0.43	400.000	SY

BRIDGE ITEMS:

BOX BRIDGE CONCRETE, CLASS BB	179.680	CY
REINFORCEMENT	35,216.000	LB