



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County Grenada

Project No. LSBP-22(10)

Road Name. Haile Road

BIDS RECEIVED: THURSDAY, NOVEMBER 12, 2026 AT 9:00 AM IN THE BOARDROOM AT GRENADA, MS

Project Description: 0.02 miles of BRIDGE and APPROACHES

ROADWAY ITEMS:

	QUANTITY	UNIT
Mobilization	1.000	LS
Clearing and Grubbing	1.000	LS
Removal of Bridge @ Sta. 0+53	1.000	UN
Removal of Inlet	1.000	UN
Removal of Pipe (All Sizes)	60.000	LF
REMOVE AND RELAY RIPRAP	85.000	SY
Unclassified Excavation (FM)	128.000	CY
Excess Excavation (FM)	711.000	CY
Crushed Stone, Size 610	200.000	TON
18" Corrugated Polyethylene Pipe	40.000	LF
Right-of-Way Markers (Type II)	4.000	EA
Maintenance of Traffic	1.000	LS
Additional Construction Signs	0.000	SF
Reflectorized Traffic Object Marker (Encapsulated Lens) (Type 3)	4.000	EA

EROSION CONTROL ITEMS:

	QUANTITY	UNIT
Agricultural Limestone	0.500	TON
Commercial Fertilizer (13:13:13)	0.250	TON
Ammonium Nitrate	0.030	TON
Seeding	0.250	AC
Vegetative Materials for Mulch	0.750	TON
Temporary Silt Fence (Type II) (AOS 0.15-0.84)	300.000	LF
Wattles, 12"	100.000	LF
Loose Riprap, (300 LB.)	10.000	TON
Geotextile under RipRap, Type V, Non-Woven, AOS <0.43	20.000	SY

BRIDGE ITEMS:

	QUANTITY	UNIT
Test Pile, 18" Prestressed Concrete Piling	2.000	EA
Conventional Static Pile Load Test	0.000	EA
18" Prestressed Concrete Piling	600.000	LF
24" Preformed Pile Hole	300.000	LF
Bridge Concrete, Class "AA"	45.180	CY
Reinforcement	9,010.000	LB
19' Precast Concrete Slab Unit, 3.5' Interior	12.000	EA

31' Precast Concrete Slab Unit, 3.5' Interior	6.000	EA
19' Precast Concrete Slab Unit, 3.5' Exterior	4.000	EA
31' Precast Concrete Slab Unit, 3.5' Exterior	2.000	EA
Precast Concrete Barrier Rail	138.000	LF
Loose Riprap, (300 LB.)	320.000	TON
Geotextile under RipRap, Type V, Non-Woven, AOS <0.43	600.000	SY