



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County Harrison

Project No. LSBP-24(20)

Road Name. Saucier Advance Road

BIDS RECEIVED: WEDNESDAY, MARCH 18, 2026 AT 10:00 AM IN THE BOARDROOM AT GULFPORT, MS

Project Description: 0.028 miles of BRIDGE and APPROACHES

ROADWAY ITEMS:

	QUANTITY	UNIT
Mobilization	1.000	LS
Clearing and Grubbing	1.000	LS
Removal of Bridge @ Sta. 12+00	1.000	UN
Unclassified Excavation (FM)	98.000	CY
Excess Excavation (FM)	396.000	CY
Geotextile Fabric Stabilization (Type V) AOS < 0.43, Non-Woven	140.000	SY
Crushed Stone (Size 610)	134.000	TON
Maintenance of Traffic	1.000	LS
Additional Construction Signs	0.000	SF
Reflectorized Traffic Object Marker (Encapsulated Lens) (Type 3)	4.000	EA

EROSION CONTROL ITEMS:

	QUANTITY	UNIT
Agricultural Limestone	0.220	TON
Commercial Fertilizer (13:13:13)	0.110	TON
Seeding	0.110	AC
Vegetative Materials for Mulch	0.330	TON
Solid Sodding	100.000	SY
Temporary Silt Fence (Type I) (AOS 0.15-0.84)	290.000	LF
Wattles, 20"	100.000	LF

BRIDGE ITEMS:

	QUANTITY	UNIT
Test Piles, 14", Prestressed Concrete	2.000	EA
Conventional Static Pile Load Test	0.000	EA
14" Prestressed Concrete Piling	1,060.000	LF
18" Preformed Pile Hole	500.000	LF
19' Precast Concrete Slab Unit, 3.5' Interior	24.000	EA
31' Precast Concrete Slab Unit, 3.5' Interior	6.000	EA
19' Precast Concrete Slab Unit, Curb	8.000	EA
31' Precast Concrete Slab Unit, Curb	2.000	EA
Beam Type Railing with Concrete Posts	214.000	LF
29' Precast Concrete Cap, Intermediate Unit, Concrete Pile	4.000	EA
29' Precast Concrete Cap, End Unit, Concrete Pile	2.000	EA
7.5' Precast Concrete Wing	4.000	EA
Loose Rip-Rap (300 LB)	190.000	TON

Geotextile under Rip-Rap (Type V) AOS < 0.43, Non-Woven

445.000

SY