



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County Hinds
Project No. LSBP-25(57)
Road Name. Buck Reed Road

BIDS RECEIVED: WEDNESDAY, APRIL 15, 2026 AT 10:00 AM IN THE BOARDROOM AT JACKSON, MS

Project Description: 0.047 miles of BOX CULVERT and APPROACHES

ROADWAY ITEMS:

Mobilization	1.000	LS
Clearing and Grubbing	1.000	LS
Removal Of Precast Concrete Bridge @ Sta. 12+96.85	1.000	UN
Removal Of Asphalt Pavement	440.000	SY
Unclassified Excavation (FM)	647.000	CY
Borrow Excavation (Contractor-Furnished FME, Class 9)	853.000	CY
Crushed Stone [size 610]	321.000	TON
Class "BB" Structural Concrete	150.000	CY
Reinforcing Steel	30,582.000	LB
18" Reinforced Concrete Pipe, Class III	24.000	LF
18" Reinforced Concrete Pipe, End Section	1.000	EA
18" Branch Connection (R.C.P. to Wingwall of Box)	1.000	EA
Right-of-Way Markers (Type II)	10.000	EA
Maintenance of Traffic	1.000	LS
Additional Construction Signs	0.000	SF

EROSION CONTROL ITEMS:

Agricultural Limestone	1.200	TON
Commercial Fertilizer (13:13:13)	0.450	TON
Seeding	0.450	AC
Vegetative Materials for Mulch	1.200	TON
Solid Sodding	200.000	SY
Temporary Silt Fence (Type II) (AOS .15 - .84)	660.000	LF
Wattles, 20"	300.000	LF
Loose Riprap, (300 Lb.)	224.000	TON
Geotextile under Rip Rap (Type V)(AOS < 0.43)(Non-Woven)	415.000	SY