



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)  
AND  
COUNTY BOARD OF SUPERVISORS**

**County** Hinds  
**Project No.** LSBP-25(59)  
**Road Name.** Moses Road

**BIDS RECEIVED:** WEDNESDAY, JUNE 24, 2026 AT 10:00 AM IN THE BOARDROOM AT JACKSON, MS

**Project Description:** 0.08 miles of BRIDGE and APPROACHES

**ROADWAY ITEMS:**

|                                                                  |         |     |
|------------------------------------------------------------------|---------|-----|
| Mobilization                                                     | 1.000   | LS  |
| Clearing and Grubbing                                            | 1.000   | LS  |
| Removal of Precast Concrete Bridge @ Sta. 12+48.57               | 1.000   | UN  |
| Removal of Detour Bridge @ Sta. 12+48.57                         | 1.000   | LS  |
| Removal of Asphalt Pavement                                      | 818.000 | SY  |
| Unclassified Excavation (FM)                                     | 207.000 | CY  |
| Borrow Excavation (Contractor Furnished FME, Class 9)            | 210.000 | CY  |
| Crushed Stone (Size 610)                                         | 387.000 | TON |
| Right-of-Way Markers (Type II)                                   | 8.000   | EA  |
| Maintenance of Traffic                                           | 1.000   | LS  |
| Additional Construction Signs                                    | 0.000   | SF  |
| Reflectorized Traffic Object Marker (Encapsulated Lens) (Type 3) | 4.000   | EA  |

**EROSION CONTROL ITEMS:**

|                                                  |           |     |
|--------------------------------------------------|-----------|-----|
| Agricultural Limestone                           | 1.200     | TON |
| Commercial Fertilizer (13:13:13)                 | 0.600     | TON |
| Seeding                                          | 0.600     | AC  |
| Vegetative Materials for Mulch                   | 1.800     | TON |
| Temporary Silt Fence (Type II) (AOS 0.15 - 0.84) | 1,000.000 | LF  |
| Wattles, 20"                                     | 200.000   | LF  |

**BRIDGE ITEMS:**

|                                                                                   |         |    |
|-----------------------------------------------------------------------------------|---------|----|
| Test Pile, 14", Concrete                                                          | 2.000   | EA |
| Conventional Static Pile Load Test                                                | 0.000   | EA |
| 14" Prestressed Concrete Piling                                                   | 660.000 | LF |
| 18" Preformed Pile Hole                                                           | 380.000 | LF |
| 19' Precast Concrete Slab Unit, 3.5' Interior, 30° Skew, Lt. Fwd.                 | 12.000  | EA |
| 31' Precast Concrete Slab Unit, 3.5' Interior, 30° Skew, Lt. Fwd.                 | 6.000   | EA |
| 19' Precast Concrete Slab Unit, Curb, 30° Skew, Lt. Fwd.                          | 4.000   | EA |
| 31' Precast Concrete Slab Unit, Curb, 30° Skew, Lt. Fwd.                          | 2.000   | EA |
| Beam-Type Railing with Concrete and Steel Posts                                   | 138.000 | LF |
| 33.50' Precast Concrete Cap, Intermediate Unit, Concrete Pile, 30° Skew, Lt. Fwd. | 2.000   | EA |
| 33.50' Precast Concrete Cap, End Unit, Concrete Pile, 30° Skew, Lt. Fwd.          | 2.000   | EA |
| 9.33' Precast Concrete Wing                                                       | 4.000   | EA |

|                                                             |         |     |
|-------------------------------------------------------------|---------|-----|
| Loose Riprap, 300 Lb.                                       | 207.000 | TON |
| Geotextile under Rip Rap, (Type V) (AOS < 0.43) (Non-Woven) | 353.000 | SY  |