



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County Hinds
Project No. LSBP-25(60)
Road Name. Learned Oakley Road

BIDS RECEIVED: WEDNESDAY, APRIL 15, 2026 AT 10:00 AM IN THE BOARDROOM AT JACKSON, MS

Project Description: 0.086 miles of BRIDGE and APPROACHES

ROADWAY ITEMS:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF PRECAST CONCRETE BRIDGE @ Sta. 12+98.31	1.000	UN
REMOVAL OF ASPHALT PAVEMENT	687.000	SY
UNCLASSIFIED EXCAVATION (FM)	405.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9)	913.000	CY
CRUSHED STONE (SIZE 610)	426.000	TON
24" CORRUGATED POLYETHYLENE PIPE	32.000	LF
RIGHT-OF-WAY MARKERS (TYPE II)	9.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	1.200	TON
COMMERCIAL FERTILIZER (13:13:13)	0.600	TON
SEEDING	0.600	AC
VEGETATIVE MATERIALS FOR MULCH	1.800	TON
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15 - 0.84)	1,063.000	LF
WATTLES, 20"	300.000	LF

BRIDGE ITEMS:

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14" PRESTRESSED CONCRETE PILING	940.000	LF
18" PRE-FORMED PILE HOLES	200.000	LF
40' PRECAST CONCRETE SLAB UNIT, 3.5 ' INTERIOR	18.000	EA
40' PRECAST CONCRETE SLAB UNIT, 3.5 ' EXTERIOR	6.000	EA
PRECAST CONCRETE BARRIER RAIL	240.000	LF
31.33' PRECAST CONCRETE CAP, INTERMEDIATE UNIT (CONCRETE PILE)	2.000	EA
31.00' PRECAST CONCRETE CAP, END UNIT (CONCRETE PILE)	2.000	EA
9.25' PRECAST CONCRETE WING	4.000	EA
LOOSE RIPRAP, 300 LB.	861.000	TON
GEOTEXTILE UNDER RIP RAP (TYPE V)(AOS < 0.43) (NON-WOVEN)	1,630.000	SY

