



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County Hinds
Project No. LSBP-25(61)
Road Name. West Flowers Road

BIDS RECEIVED: WEDNESDAY, JUNE 24, 2026 AT 10:00 AM IN THE BOARDROOM AT JACKSON, MS

Project Description: 0.057 miles of BRIDGE and APPROACHES

ROADWAY ITEMS:

	QUANTITY	UNIT
Mobilization	1.000	LS
Clearing and Grubbing	1.000	LS
Removal of Precast Concrete Bridge @ Sta. 15+95.72	1.000	UN
Removal of Detour Bridge @ Sta. 15+95.72	1.000	LS
Removal of Asphalt Pavement	513.000	SY
Unclassified Excavation (FM)	455.000	CY
Excess Excavation (FM)	32.000	CY
Crushed Stone (Size 610)	266.000	TON
Right-of-Way Markers (Type II)	8.000	EA
Maintenance of Traffic	1.000	LS
Additional Construction Signs	0.000	SF
Reflectorized Traffic Object Marker (Encapsulated Lens) Type 3	4.000	EA

EROSION CONTROL ITEMS:

	QUANTITY	UNIT
Agricultural Limestone	1.200	TON
Commercial Fertilizer (13:13:13)	0.450	TON
Seeding	0.450	AC
Vegetative Materials for Mulch	1.200	TON
Temporary Silt Fence (Type II) (AOS .15-.84)	830.000	LF
Wattles, 20"	300.000	LF
Loose Riprap (300 Lb.)	50.000	TON
Geotextile under Rip Rap (Type V) (AOS<0.43) (Non-Woven)	92.000	SY

BRIDGE ITEMS:

	QUANTITY	UNIT
Test Pile, 14", Concrete	2.000	EA
Conventional Static Pile Load Test	0.000	EA
14" Prestressed Concrete Piling	680.000	LF
18" Pre-formed Pile Hole	400.000	LF
31' Precast Concrete Slab Unit, 3.5' Interior	18.000	EA
31' Precast Concrete Slab Unit, 3.5' Exterior	6.000	EA
Precast Concrete Barrier Rail	186.000	LF
31' Precast Concrete Cap, Intermediate Unit (Concrete Pile)	2.000	EA
31' Precast Concrete Cap, End Unit (Concrete Pile)	2.000	EA
9.25' Precast Concrete Wing	4.000	EA

Loose Riprap (300 Lb.)	136.000	TON
Geotextile under Rip Rap (Type V) (AOS<0.43) (Non-Woven)	252.000	SY