



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)

AND

COUNTY BOARD OF SUPERVISORS

County Holmes

Project No. LSBP-26(22)

Road Name. SMITH-BAILEY ROAD

BIDS RECEIVED: TUESDAY, JULY 1, 2025 AT 10:00 AM IN THE BOARDROOM AT LEXINGTON, MS

Project Description: 0.089 miles of BRIDGE & APPROACHES

Roadway Items:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF PRECAST BRIDGE @STA. 11+98	1.000	UN
REMOVAL OF FENCE	190.000	LF
REMOVAL OF PIPE (ALL SIZES)	55.000	LF
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED, CLASS 9)	520.000	CY
GRANULAR MATERIAL (LVM), (CLASS 4, GROUP B)	360.000	CY
18" ALUMINUM COATED CORRUGATED METAL PIPE (16 GAUGE) (3:1 CORRUGATION)	60.000	LF
24" ALUMINUM COATED CORRUGATED METAL PIPE (16 GAUGE) (3:1 CORRUGATION)	60.000	LF
RIGHT-OF-WAY MARKERS (TYPE II)	10.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	1.980	TON
COMMERCIAL FERTILIZER (13:13:13)	0.990	TON
SEEDING	0.990	AC
VEGETATIVE MATERIALS FOR MULCH	2.970	TON
TEMPORARY SILT FENCE (TYPE I) (AOS 0.15-0.84)	1,140.000	LF
WATTLES, 20"	100.000	LF
LOOSE RIPRAP, 300 LB.	230.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V (NON-WOVEN), AOS <0.43	230.000	SY

BRIDGE ITEMS:

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14" PRESTRESSED CONCRETE PILING	800.000	LF
18" PRE-FORMED PILE HOLES	200.000	LF
BRIDGE CONCRETE, CLASS B	5.000	CY
REINFORCEMENT	575.000	LB
31' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR	18.000	EA
31' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR	6.000	EA
PRECAST CONCRETE BARRIER RAIL	186.000	LF
31.0 ' PRECAST CONCRETE CAP, INTERMEDIATE UNIT CONCRETE PILE	2.000	EA
31.0 ' PRECAST CONCRETE CAP, END UNIT CONCRETE PILE	2.000	EA

9.25' PRECAST CONCRETE WING	4.000	EA
LOOSE RIPRAP, 300 LB.	200.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V (NON-WOVEN), AOS <0.43	200.000	SY