



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County	Jackson
Project No.	LSBP-30(18)
Road Name.	CONSTITUTION ROAD

BIDS RECEIVED: WEDNESDAY, NOVEMBER 12, 2025 AT 12:00 PM IN THE BOARDROOM AT PASCAGOULA, MS

Project Description: 0.26 miles of BRIDGE and APPROACHES

ROADWAY ITEMS:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF OBSTRUCTIONS	1.000	LS
REMOVAL OF BRIDGE @ STA. 17+94	1.000	UN
REMOVAL OF ASPHALT (ALL DEPTHS)	2,550.000	SY
REMOVAL OF CONCRETE (ALL DEPTHS)	40.000	SY
UNCLASSIFIED EXCAVATION (FM)	2,502.000	CY
BORROW EXCAVATION (CONTRACTOR FURNISHED, LVM, CLASS 7)	2,819.000	CY
EXCESS EXCAVATION (LVM)	5,527.000	CY
GEOGRID, TYPE III	2,459.000	SY
CRUSHED STONE (SIZE 610)	1,030.000	TON
18" CORRUGATED POLYETHYLENE PIPE	30.000	LF
GUARD RAIL, "W" BEAM	162.000	LF
GUARD RAIL, BRIDGE END SECTION, TYPE "I" THRIE BEAM	4.000	EA
GUARD RAIL, TERMINAL END SECTION	4.000	EA
RIGHT-OF-WAY MARKERS (TYPE II)	10.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS)(TYPE 3)	4.000	EA

EROSION CONTROL ITEMS:

TOPSOIL FOR SLOPE TREATMENT (CONTRACTOR FURNISHED) (LVM)	684.000	CY
AGRICULTURAL LIMESTONE	6.000	TON
COMMERCIAL FERTILIZER (13-13-13)	3.000	TON
AMMONIUM NITRATE	2.000	TON
SEEDING	3.000	AC
VEGETATIVE MATERIALS FOR MULCH	9.000	TON
SOLID SODDING	1,529.000	SY
TEMPORARY SILT FENCE (TYPE II) (AOS-0.15-0.84)	3,040.000	LF
WATTLES, 20"	640.000	LF

BRIDGE ITEMS:

TEST PILES	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	1.000	EA

14 " PRESTRESSED CONCRETE PILING	1,590.000	LF
18" PREFORMED PILE HOLE	320.000	LF
BRIDGE CONCRETE, CLASS B	7.000	CY
REINFORCEMENT	725.000	LB
31 ' PRECAST CONCRETE SLAB UNIT, 3.5 ' INTERIOR, 30 DEG SKEW, LT FWD	30.000	EA
40 ' PRECAST CONCRETE SLAB UNIT, 3.5 ' INTERIOR, 30 DEG SKEW, LT FWD	6.000	EA
31 ' PRECAST CONCRETE SLAB UNIT, 3.5 ' EXTERIOR, 30 DEG SKEW, LT FWD	10.000	EA
40 ' PRECAST CONCRETE SLAB UNIT, 3.5 ' EXTERIOR, 30 DEG SKEW, LT FWD	2.000	EA
PRECAST CONCRETE BARRIER RAIL	390.000	LF
36 ' PRECAST CONCRETE CAP, INTERMEDIATE UNIT, CONCRETE PILE, 30 DEG SKEW, LT FWD.	3.000	EA
36 ' PRECAST CONCRETE CAP, END UNIT, CONCRETE PILE, 30 DEG SKEW, LT FWD.	2.000	EA
36.17 ' PRECAST CONCRETE CAP, INTERMEDIATE UNIT, CONCRETE PILE, 30 DEG SKEW, LT FWD.	2.000	EA
11.33' PRECAST CONCRETE WING	4.000	EA
LOOSE RIPRAP, 300 LB.	191.000	TON
GEOTEXTILE UNDER RIPRAP, NON-WOVEN TYPE V, AOS <.43	354.000	SY