



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)

AND

COUNTY BOARD OF SUPERVISORS

County Jasper

Project No. LSBP-31(22)

Road Name. CR 35

BIDS RECEIVED: MONDAY, OCTOBER 5, 2026 AT 10:00 AM IN THE BOARDROOM AT BAY SPRINGS, MS

Project Description: 0.089 miles of BRIDGE & APPROACHES

Roadway Items:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF BRIDGE @ STA. 12+85.43	1.000	UN
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9)	850.000	CY
EXCESS EXCAVATION (FM)	323.000	CY
GRANULAR MATERIAL (LVM), (CLASS 9, GROUP B)	684.000	CY
SIZE 1 STABILIZER AGGREGATE, COARSE	79.000	CY
GUARD RAIL, "W" BEAM COMPLETE IN PLACE	100.000	LF
GUARD RAIL, BRIDGE END SECTION, TYPE I THRIE BEAM	4.000	EA
GUARD RAIL, TERMINAL END SECTION	4.000	EA
ROADWAY CONSTRUCTION SURVEYING	1.000	LS
RIGHT-OF-WAY MARKERS (TYPE II)	10.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
REFLECTORIZED TRAFFIC WARNING SIGN WITH SUPP PLATE (ENCAPSULATED LENS)	2.000	EA
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA

EROSION CONTROL ITEMS:

REMOVE AND RELAY RIPRAP	500.000	SY
AGRICULTURAL LIMESTONE	1.340	TON
COMMERCIAL FERTILIZER (13:13:13)	0.670	TON
SEEDING	0.670	AC
VEGETATIVE MATERIALS FOR MULCH	2.010	TON
SOLID SODDING	130.000	SY
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	1,300.000	LF
WATTLES, 20"	300.000	LF
LOOSE RIPRAP, 200 LB.	100.000	TON
LOOSE RIPRAP, 300 LB.	68.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, AOS 0.21-0.43	237.000	SY

BRIDGE ITEMS:

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14" PRESTRESSED CONCRETE PILING	920.000	LF
18" PRE-FORMED PILE HOLES	490.000	LF
31 ' PRECAST CONCRETE SLAB UNIT, 3.5 ' INTERIOR	12.000	EA

40 ' PRECAST CONCRETE SLAB UNIT, 3.5 ' INTERIOR	6.000	EA
31 ' PRECAST CONCRETE SLAB UNIT, 3.5 ' EXTERIOR	4.000	EA
40 ' PRECAST CONCRETE SLAB UNIT, 3.5 ' EXTERIOR	2.000	EA
PRECAST CONCRETE BARRIER RAIL	204.000	LF
31.33 ' PRECAST CONCRETE CAP, INTERMEDIATE UNIT, CONCRETE PILE,	2.000	EA
31" PRECAST CONCRETE CAP, END UNIT, CONCRETE PILE,	2.000	EA
9.25' PRECAST CONCRETE WING	4.000	EA
LOOSE RIPRAP, 300 LB.	136.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, AOS 0.21-0.43	190.000	SY