



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS

County Jefferson Davis
Project No. LSBP-33(23)
Road Name. Wiley Dyess Road

BIDS RECEIVED: THURSDAY, APRIL 16, 2026 AT 10:00 AM IN THE BOARDROOM AT PRENTISS, MS
Project Description: 0.023 miles of BOX BRIDGE & APPROACHES

Roadway Items:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF PRECAST BRIDGE AT STATION 10+48	1.000	UN
UNCLASSIFIED EXCAVATION (FM)	490.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 7)	480.000	CY
STRUCTURE EXCAVATION	745.000	CY
TEMPORARY STREAM DIVERSION	1.000	EA
GRANULAR MATERIAL (LVM), (CLASS 6, GROUP C)	245.000	CY
CRUSHED STONE, 610	400.000	TON
SIZE II STABILIZER AGGREGATE, COARSE	150.000	CY
RIGHT-OF-WAY MARKERS (TYPE I)	6.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	0.800	TON
COMMERCIAL FERTILIZER (13-13-13)	0.400	TON
SEEDING	0.400	AC
VEGETATIVE MATERIALS FOR MULCH	1.200	TON
SOLID SODDING	200.000	SY
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	350.000	LF
WATTLES, 20"	80.000	LF
LOOSE RIPRAP, 200 LB.	250.000	TON
GEOTEXTILE UNDER RIPRAP NON-WOVEN, TYPE V, AOS < 0.43	500.000	SY

BRIDGE ITEMS:

BOX BRIDGE CONCRETE, CLASS "BB"	222.650	CY
REINFORCEMENT	38,517.000	LB