



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)

AND

COUNTY BOARD OF SUPERVISORS

County Jefferson Davis

Project No. LSBP-33(24)

Road Name. Mt. Zion Road

BIDS RECEIVED: Tuesday, October 6, 2025, at 10:00AM at the County Boardroom at Prentiss Ms

Project Description: 0.037 miles of BRIDGE & APPROACHES

Roadway Items:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF PRECAST CONCRETE BRIDGE AT STATION 10+60	1.000	UN
UNCLASSIFIED EXCAVATION (FM)	40.000	CY
CHANNEL EXCAVATION (FM)	460.000	CY
EXCESS EXCAVATION (FM)	125.000	CY
GRANULAR MATERIAL (LVM), (CLASS 6, GROUP C)	200.000	CY
CRUSHED STONE, 610	250.000	TON
RIGHT-OF-WAY MARKERS (TYPE I)	6.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	0.600	TON
COMMERCIAL FERTILIZER (13-13-13)	0.300	TON
SEEDING	0.300	AC
VEGETATIVE MATERIALS FOR MULCH	0.900	TON
SOLID SODDING	200.000	SY
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	500.000	LF
WATTLES, 20"	100.000	LF
LOOSE RIPRAP, 200 LB.	100.000	TON
LOOSE RIPRAP, 300 LB.	100.000	TON
GEOTEXTILE UNDER BRIDGE ABUTMENT NON-WOVEN, TYPE V, AOS < 0.43	100.000	SY
GEOTEXTILE UNDER RIPRAP NON-WOVEN, TYPE V, AOS < 0.43	400.000	SY

BRIDGE ITEMS:

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14 " PRESTRESSED CONCRETE PILING	730.000	LF
18" PRE-FORMED PILE HOLE	140.000	LF
31 ' PRECAST CONCRETE SLAB UNIT, 3'-6" INTERIOR	18.000	EA
31 ' PRECAST CONCRETE SLAB UNIT, CURB	6.000	EA
BEAM TYPE RAILING WITH CONCRETE POSTS	186.000	LF
29' PRECAST CONCRETE CAP, INTERMEDIATE UNIT, CONCRETE PILE	2.000	EA
29' PRECAST CONCRETE CAP, END UNIT, CONCRETE PILE	2.000	EA

7.5' PRECAST CONCRETE WING	4.000	EA
LOOSE RIPRAP, 300 LB.	95.000	TON
GEOTEXTILE UNDER RIPRAP NON-WOVEN, TYPE V, AOS < 0.43	246.000	SY