



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)

AND

COUNTY BOARD OF SUPERVISORS

County Jones

Project No. LSBP-34(29)

Road Name. Phillips Road East

BIDS RECEIVED: TUESDAY, JULY 29, 2025 AT 10:30 AM IN THE COURTHOUSE AT LAUREL, MS

Project Description: 0.133 miles of BRIDGE & APPROACHES

Roadway Items:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF PRECAST BRIDGE @ STATION 15+02.55	1.000	UN
REMOVAL OF PIPE (ALL SIZES)	64.000	LF
UNCLASSIFIED EXCAVATION (FM)	281.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9)	4,018.000	CY
CRUSHED STONE (SIZE 825)	848.000	TON
28 " X 18 " REINFORCED CONCRETE ARCH PIPE,CLASS III	24.000	LF
36 " X 22 " REINFORCED CONCRETE ARCH PIPE,CLASS III	40.000	LF
GUARD RAIL, "W" BEAM	50.000	LF
GUARD RAIL, BRIDGE END SECTION, TYPE I THRIE BEAM	4.000	EA
GUARD RAIL, TERMINAL END SECTION	4.000	EA
ROADWAY CONSTRUCTION SURVEYING	1.000	LS
RIGHT-OF-WAY MARKERS (TYPE II)	10.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA
REFLECTORIZED TRAFFIC DELINEATOR SIGN (ENCAPSULATED LENS)	16.000	EA
REFLECTORIZED TRAFFIC WARNING SIGN WITH SUPP. PLATE (ENCAPSULATED LENS)	2.000	EA
GEOTEXTILE FABRIC UNDER BRIDGE END TREATMENT, TYPE V, AOS<0.43, NON-WOVEN	114.000	SY

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	2.460	TON
COMMERCIAL FERTILIZER (13:13:13)	1.230	TON
SEEDING	1.230	AC
VEGETATIVE MATERIALS FOR MULCH	2.460	TON
SOLID SODDING	50.000	SY
TEMPORARY GRASSING	1.230	ACRE
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	1,414.000	LF
WATTLES, 20" DIAMETER	500.000	LF

BRIDGE ITEMS:

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14 " PRESTRESSED CONCRETE PILING	580.000	LF
18 " PRE-FORMED PILE HOLES	401.000	LF

40 ' PRECAST CONCRETE SLAB UNIT, 3.5 ' INTERIOR	18.000	EA
40 ' PRECAST CONCRETE SLAB UNIT, EXTERIOR	6.000	EA
PRECAST CONCRETE BARRIER RAIL	240.000	LF
31.17 ' PRECAST CONCRETE CAP, INTERMEDIATE UNIT, CONC. PILE	2.000	EA
31.17 ' PRECAST CONCRETE CAP, END UNIT, CONC. PILE	2.000	EA
9.17' PRECAST CONCRETE WING	4.000	EA
LOOSE RIPRAP, 300 LB.	197.000	TON
GEOTEXTILE FABRIC UNDER RIPRAP NON-WOVEN, TYPE V, AOS<0.43	413.000	SY