



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County Kemper
Project No. LSBP-35(25)
Road Name. OLD DEKALB-SCOOBA ROAD

BIDS RECEIVED: FRIDAY, JUNE 19, 2026 AT 10:00 AM IN THE SUPERVISOR'S ANNEX AT DE KALB, MS

Project Description: 0.046 miles of BOX BRIDGE and APPROACHES

ROADWAY ITEMS:

	QUANTITY	UNIT
Mobilization	1.000	LS
Clearing and Grubbing	1.000	LS
Removal of Precast Concrete Bridge at STA. 17+42.51	1.000	UN
Unclassified Excavation (FM)	1,331.000	CY
Borrow Excavation (Contractor Furnished FME, Class 9)	500.000	CY
Channel Excavation (FM)	91.000	CY
Excess Excavation (FM)	309.000	CY
Temporary Stream Diversion	1.000	EA
Granular Material (LVM), (Class 9, Group B)	174.000	CY
Size I Stabilizer Aggregate, Coarse	47.000	CY
Class "C" Structural Concrete	37.000	CY
Right-of-Way Markers (Type II)	7.000	EA
Maintenance of Traffic	1.000	LS
Additional Construction Signs	0.000	SF

EROSION CONTROL ITEMS:

	QUANTITY	UNIT
Solid Sodding	150.000	SY
Excelsior Blanket	500.000	SY
Hydroseeding, Temporary Grassing	0.360	AC
Temporary Silt Fence (Type II) (AOS 0.15-0.84)	500.000	LF
Wattles, 20"	150.000	LF
Loose Riprap, (200 LB.)	150.000	TON
Geotextile under Riprap, Type V, AOS<0.43, Non-Woven	300.000	SY

BOX BRIDGE ITEMS:

	QUANTITY	UNIT
Box Bridge Concrete, Class "BB"	192.530	CY
Reinforcement	41,869.000	LB