



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)

AND

COUNTY BOARD OF SUPERVISORS

County Lauderdale
Project No. LSBP-38(36)
Road Name. MURPHY ROAD

BIDS RECEIVED: Friday, April 26, 2024, 10:00a.m. at Meridian, MS

Project Description: 0.07 miles of BOX BRIDGE & APPROACHES

Roadway Items:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF BRIDGE AT STA. 14+99.34	1.000	UN
UNCLASSIFIED EXCAVATION (FM)	8,700.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9)	1,500.000	CY
EXCESS EXCAVATION (FM)	5,932.000	CY
GRANULAR MATERIAL (LVM), (CLASS 9, GROUP B)	373.000	CY
SIZE I STABILIZER AGGREGATE, COARSE	53.000	CY
CLASS "C" STRUCTURAL CONCRETE	56.000	CY
15 in REINFORCED CONCRETE PIPE, CLASS III	32.000	LF
RIGHT-OF-WAY MARKERS (TYPE II)	9.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF

EROSION CONTROL ITEMS:

SOLID SODDING	175.000	SY
HYDROSEEDING	0.950	AC
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	750.000	LF
WATTLES, 20 in DIAMETER	200.000	LF
LOOSE RIPRAP, 300 LB.	180.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, AOS 0.21-0.43	400.000	SY

BOX BRIDGE ITEMS:

BOX BRIDGE CONCRETE, CLASS "BB"	291.930	CY
REINFORCEMENT	56,284.430	LB