



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County	Lee
Project No.	LBSP-41(37)
Road Name.	County Road 185

BIDS RECEIVED: WEDNESDAY, NOVEMBER 12, 2025 AT 10:00 AM IN THE BOARDROOM AT TUPELO, MS

Project Description: 0.121 miles of BRIDGE and APPROACHES Road A - Bridge Replacement, Road B - Concrete Arch Pipe

ROADWAY ITEMS:

Mobilization	1.000	LS
Clearing and Grubbing	1.000	LS
Removal of Bridge At Sta. 71+97	1.000	UN
Removal of Pavement (All Thicknesses)	1,600.000	SY
Unclassified Excavation (FM)	1,036.000	CY
Borrow Excavation (F.M.E.) (Contractor Furnished) (Class 9)	256.000	CY
Channel Excavation (FM)	292.000	CY
Geotextile Fabric Stabilization (Type V, Non-Woven) (AOS<0.43)	2,552.000	SY
Crushed Stone (Size 3/4" & Down) (FM)	530.000	CY
Class "B" Structural Concrete, Minor Structures	0.166	CY
29" x 18" Reinforced Concrete Arch Pipe, Class A-III	56.000	LF
29" x 18" Reinforced Concrete Arch Pipe, End Section	2.000	EA
Right-of-Way Markers (Type II)	13.000	EA
Maintenance of Traffic	1.000	LS
Additional Construction Signs	0.000	SF
Reflectorized Traffic Object Marker (Encapsulated Lens) (Type 3)	4.000	EA

EROSION CONTROL ITEMS:

Agricultural Limestone	0.630	TON
Commercial Fertilizer (13-13-13)	0.630	TON
Seeding	1.250	AC
Vegetative Materials for Mulch	3.750	TON
Solid Sodding	100.000	SY
Temporary Silt Fence (Type I or II) (AOS 0.15-0.84)	305.000	LF
Wattles, 20"	200.000	LF
Loose Riprap, 300 Lb.	220.000	TON
Geotextile under Riprap, Type V, AOS<0.43 (Non-Woven)	318.000	SY

BRIDGE ITEMS:

Test Pile	2.000	EA
Conventional Static Pile Load Test	0.000	EA
12" Steel Piling	640.000	LF
18" Preformed Pile Hole	480.000	LF
Bridge Concrete, Class A	97.580	CY

80' Prestressed Concrete Beam, Type III	398.750	LF
Reinforcement	21,463.000	LB
Concrete Railing	160.000	LF
Loose Riprap, 300 Lb.	144.000	TON
Geotextile under Riprap, Type V, AOS<0.43 (Non-Woven)	128.000	SY