



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)

AND

COUNTY BOARD OF SUPERVISORS

**County** Lincoln  
**Project No.** LSBP-43(53)  
**Road Name.** OPELOUSAS LANE NW

**BIDS RECEIVED:** Wednesday, May 17, 2024 @10 AM IN THE LINCOLN COUNTY BOARDROOM AT BROOKHAVEN, MS

**Project Description:** 0.085 miles of BOX CULVERT & APPROACHES

Roadway Items:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF BRIDGE @ STATION 11+87.35	1.000	UN
UNCLASSIFIED EXCAVATION (PM)	405.000	CY
BORROW EXCAVATION (CONTRACTOR FURNISHED, LVM, CLASS 7)	1,350.000	CY
EXCESS EXCAVATION (LVM)	475.000	CY
STRUCTURE EXCAVATION	475.000	CY
TEMPORARY STREAM DIVERSION	1.000	EA
GRANULAR MATERIAL (LVM), (CLASS 4, GROUP B)	530.000	CY
CLASS "BB" STRUCTURAL CONCRETE	149.520	CY
REINFORCING STEEL	28,904.000	LB
FILTER MATERIAL FOR FILTER BEDS, TYPE A	160.000	CY
RIGHT-OF-WAY MARKERS (TYPE II)	13.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF

EROSION CONTROL ITEMS:

COMMERCIAL FERTILIZER (13-13-13)	0.970	TON
SEEDING	0.970	AC
VEGETATIVE MATERIALS FOR MULCH	2.910	TON
SOLID SODDING	200.000	SY
EROSION MAT	286.000	SY
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	1,000.000	LF
WATTLES, 20 INCH	160.000	LF
LOOSE RIPRAP, 300 LB.	250.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V NON-WOVEN, AOS < 0.21-0.43	300.000	SY