OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS

County Lincoln
Project No. LSBP-43(57)
Road Name. Callender Road NE

BIDS RECEIVED: TUESDAY, DECEMBER 15, 2026 AT 10:00 AM IN THE BOARDROOM AT BROOKHAVEN, MS
Project Description: 0.11 miles of BRIDGE and APPROACHES

ROADWAY ITEMS:	QUANTITY	UNIT
Mobilization	1.000	LS
Clearing and Grubbing	1.000	LS
Removal of Precast Bridge @ Sta. 12+32.85	1.000	UN
Unclassified Excavation (FM)	607.000	CY
Borrow Excavation (Contractor Furnished, LVM, Class 7)	400.000	CY
Channel Excavation (FM)	510.000	CY
Granular Material (LVM), (Class 6, Group C)	486.000	CY
Crushed Stone 610	210.000	TON
Right-of-Way Markers (Type II)	6.000	EA
Maintenance of Traffic	1.000	LS
Additional Construction Signs	0.000	SF
Reflectorized Traffic Object Marker (Encapsulated Lens) (Type 3)	4.000	EA
Geotextile under Riprap, Type V Non-Woven, AOS < 0.43	100.000	SY

EROSION CONTROL ITEMS:	QUANTITY	UNIT
Commercial Fertilizer (13-13-13)	1.000	TON
Seeding	1.000	AC
Vegetative Materials for Mulch	3.000	TON
Solid Sodding	200.000	SY
Temporary Silt Fence (Type II) (AOS 0.15-0.84)	1,240.000	LF
Erosion Mat	45.000	SY
Wattles, 20"	200.000	LF

BRIDGE ITEMS:	QUANTITY	UNIT
Test Piles, 14" Concrete	2.000	EA
Conventional Static Pile Load Test	0.000	EA
14" Prestressed Concrete Piling	520.000	LF
18” Pre-formed Pile Holes	360.000	LF
19' Precast Concrete Slab Unit, 3'-6" Interior	12.000	EA
31' Precast Concrete Slab Unit, 3'-6" Interior	6.000	EA
19' Precast Concrete Slab Unit, Curb	4.000	EA
31' Precast Concrete Slab Unit, Curb	2.000	EA
Beam Type Railing with Concrete Posts	138.000	LF
29' Precast Concrete Cap Intermediate Unit, Concrete Pile	2.000	EA

29' Precast Concrete Cap End Unit, Concrete Pile	2.000	EA
7.5' Precast Concrete Wing	4.000	EA
Loose Riprap, 300 lb.	491.000	TON
Geotextile under Riprap, Type V Non-Woven, AOS < 0.43	593.000	SY