



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County	Lowndes
Project No.	LSBP-44(17)
Road Name.	Old Wolfe Road

BIDS RECEIVED: TUESDAY, NOVEMBER 24, 2026 AT 10:00 AM IN THE SUPERVISOR'S BOARDROOM AT COLUMBUS, MS

Project Description: 0.189 miles of BOX BRIDGE and APPROACHES

ROADWAY ITEMS:	QUANTITY	UNIT
MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF FENCE	42.000	LF
REMOVAL OF ASPHALT (ALL Types) (All Depths)	2,300.000	SY
REMOVAL OF PIPE (ALL SIZES)	225.000	LF
UNCLASSIFIED EXCAVATION (F.M.)	2,523.000	CY
BORROW EXCAVATION (Contractor Furnished F.M.E., Class B-9-6)	400.000	CY
EXCESS EXCAVATION (F.M.)	1,090.000	CY
PORTLAND CEMENT CONCRETE PAVED DITCH	4.000	CY
TEMPORARY STREAM DIVERSION	1.000	EA
GRANULAR MATERIAL (LVM), (CLASS 3, GROUP B)	1,357.000	CY
ASPHALT, ST 9.5MM	220.000	TON
ASPHALT, ST 12.5MM	650.000	TON
CLASS B STRUCTURAL CONCRETE, MINOR STRUCTURES	9.616	CY
REINFORCING STEEL	478.000	LB
18" REINFORCED CONCRETE PIPE, CLASS III	75.000	LF
24" REINFORCED CONCRETE PIPE, CLASS III	48.000	LF
18" REINFORCED CONCRETE PIPE, END SECTION	3.000	EA
24" REINFORCED CONCRETE PIPE, END SECTION	2.000	EA
24" CORRUGATED POLYETHYLENE PIPE	530.000	LF
18" BRANCH CONNECTION AT WINGWALL	1.000	EA
24" BRANCH CONNECTION AT WINGWALL	1.000	EA
CASTINGS	323.000	LB
GRATINGS	200.000	LB
CONCRETE DRIVEWAY	45.000	SY
COMBINATION CONCRETE CURB AND GUTTER	344.000	LF
RIGHT-OF-WAY MARKERS (TYPE II)	20.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4" WIDE THERMOPLASTIC EDGE STRIPE (CONT. WHITE) 60 MILS	0.186	MI
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONT. YELLOW) 90 MILS	980.000	LF
THERMOPLASTIC LEGEND (WHITE) (120 MILS)	45.000	LF

EROSION CONTROL ITEMS:

QUANTITY UNIT

AGRICULTURAL LIMESTONE	3.880	TON
COMMERCIAL FERTILIZER (13-13-13)	1.940	TON
SEEDING	1.940	AC
VEGETATIVE MATERIALS FOR MULCH	5.820	TON
SOLID SODDING	50.000	SY
TEMPORARY SILT FENCE (TYPE I) (AOS 0.15-0.84)	3,000.000	LF
WATTLES, 20"	100.000	LF

BOX BRIDGE ITEMS:

	QUANTITY	UNIT
BOX BRIDGE CONCRETE, CLASS BB	297.590	CY
REINFORCEMENT	50,384.000	LB
LOOSE RIPRAP, 100 LB.	50.000	TON
LOOSE RIPRAP, 200 LB.	370.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, NON-WOVEN (AOS<0.43)	658.000	SY