



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)

AND

COUNTY BOARD OF SUPERVISORS

County Madison

Project No. LSBP-45(23)

Road Name. Loring Road

BIDS RECEIVED: TUESDAY, JULY 29, 2025 AT 10:00 AM IN THE CONFERENCE ROOM AT CANTON, MS

Project Description: 0.36 miles of BRIDGE & APPROACHES

Roadway Items:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF PRECAST BRIDGE @ STATION 19+56.44	1.000	UN
REMOVAL OF ASPHALT PAVEMENT (ALL DEPTHS)	2,981.000	SY
UNCLASSIFIED EXCAVATION (PM)	1,627.000	CY
CHANNEL EXCAVATION (FM)	290.000	CY
EXCESS EXCAVATION (FM)	7,811.000	CY
GRANULAR MATERIAL, (CLASS 5, GROUP C)	1,120.000	TON
CRUSHED STONE	801.000	TON
COLD MILLING OF BITUMINOUS PAVEMENT, ALL DEPTHS	250.000	SY
18" REINFORCED CONCRETE PIPE, CLASS III	32.000	LF
GUARD RAIL, "W" BEAM, COMPLETE IN PLACE	250.000	LF
GUARD RAIL, BRIDGE END SECTION, TYPE "I" THRIE BEAM, COMPLETE IN PLACE	4.000	EA
GUARD RAIL, TERMINAL END SECTION	4.000	EA
CONSTRUCTION SURVEYING	1.000	LS
BRIDGE CONSTRUCTION SURVEYING	1.000	LS
RIGHT-OF-WAY MARKERS (TYPE II)	5.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA
GEOTEXTILE UNDER BRIDGE END TREATMENT, TYPE V, NON-WOVEN (AOS<0.43)	68.000	SY

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	3.000	TON
COMMERCIAL FERTILIZER (13-13-13)	2.000	TON
AMMONIUM NITRATE	1.000	TON
SEEDING	2.000	AC
VEGETATIVE MATERIALS FOR MULCH	5.000	TON
TEMPORARY SILT FENCE (TYPE II) (AOS<0.43)	6,643.000	LF
WATTLES, 20"	400.000	LF

BRIDGE ITEMS:

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14" PRESTRESSED CONCRETE PILING	630.000	LF
18" PRE-FORMED PILE HOLES	455.000	LF

CONCRETE PILING CUT-OFF, 14"	0.000	EA
31' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR	18.000	EA
31' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR	6.000	EA
PRECAST CONCRETE BARRIER RAIL	186.000	LF
31' PRECAST CONCRETE CAP, INTERMEDIATE UNIT, CONCRETE PILE	2.000	EA
31' PRECAST CONCRETE CAP, END UNIT, CONCRETE PILE	2.000	EA
9.25' PRECAST CONCRETE WING	4.000	EA
LOOSE RIPRAP, 300 LB.	544.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, NON-WOVEN (AOS<0.43)	520.000	SY