



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)

AND

COUNTY BOARD OF SUPERVISORS

County Marion
Project No. LSBP-46(20)
Road Name. EBENEZER CHURCH ROAD

BIDS RECEIVED: WEDNESDAY, MAY 20, 2026 AT 10:00 AM IN THE BOARDROOM AT COLUMBIA, MS

Project Description: 0.085 miles of BRIDGE & APPROACHES

Roadway Items:

| | | |
|---|-----------|----|
| MOBILIZATION | 1.000 | LS |
| CLEARING AND GRUBBING | 1.000 | LS |
| REMOVAL OF BRIDGE @ STA. 11+79.00 | 1.000 | UN |
| UNCLASSIFIED EXCAVATION (FM) | 223.000 | CY |
| BORROW EXCAVATION (CONTRACTOR FURNISHED, LVM, CLASS 7) | 1,173.000 | CY |
| GRANULAR MATERIAL (LVM), (CLASS 6, GROUP C) | 440.000 | CY |
| CLASS "B" STRUCTURAL CONCRETE, MINOR STRUCTURES | 0.332 | CY |
| 24" REINFORCED CONCRETE PIPE, CLASS C | 64.000 | LF |
| 24" REINFORCED CONCRETE PIPE, END SECTION | 4.000 | EA |
| RIGHT-OF-WAY MARKERS (TYPE II) | 12.000 | EA |
| MAINTENANCE OF TRAFFIC | 1.000 | LS |
| ADDITIONAL CONSTRUCTION SIGNS | 0.000 | SF |
| REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3) | 4.000 | EA |

EROSION CONTROL ITEMS:

| | | |
|---|---------|-----|
| COMMERCIAL FERTILIZER (13-13-13) | 0.750 | TON |
| SEEDING | 0.750 | AC |
| VEGETATIVE MATERIALS FOR MULCH | 1.500 | TON |
| TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84) | 850.000 | LF |
| WATTLES, 20" | 160.000 | BL |
| LOOSE RIPRAP, 200 LB. | 40.000 | TON |
| GEOTEXTILE FABRIC UNDER RIPRAP, TYPE V, AOS <0.43 | 17.000 | SY |

BRIDGE ITEMS:

| | | |
|--|---------|----|
| TEST PILE, 14" CONCRETE | 2.000 | EA |
| CONVENTIONAL STATIC PILE LOAD TEST | 0.000 | EA |
| 14 " PRESTRESSED CONCRETE PILING | 520.000 | LF |
| 18" PRE-FORMED PILE HOLES | 160.000 | LF |
| 19' PRECAST CONCRETE SLAB UNIT, 3.5 ' INTERIOR | 12.000 | EA |
| 31' PRECAST CONCRETE SLAB UNIT, 3.5 ' INTERIOR | 6.000 | EA |
| 19 ' PRECAST CONCRETE SLAB UNIT, 3.5 ' EXTERIOR | 4.000 | EA |
| 31' PRECAST CONCRETE SLAB UNIT, 3.5 ' EXTERIOR | 2.000 | EA |
| PRECAST CONCRETE BARRIER RAIL | 138.000 | LF |
| 31 ' PRECAST CONCRETE CAP, INTERMEDIATE UNIT, CONCRETE PILE, | 2.000 | EA |
| 31' PRECAST CONCRETE CAP, END UNIT, CONCRETE PILE, | 2.000 | EA |
| 9.25' PRECAST CONCRETE WING | 4.000 | EA |

| | | |
|--|---------|-----|
| LOOSE RIPRAP, 300 LB. | 238.000 | TON |
| GEOTEXTILE UNDER LOOSE RIPRAP, TYPE V, AOS <0.43 | 253.000 | SY |