



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)

AND

COUNTY BOARD OF SUPERVISORS

County Marshall

Project No. LSBP-47(19)

Road Name. FRENCH ROAD

BIDS RECEIVED: Monday, September 21, 2026 in the Boardroom at Holly Springs, MS

Project Description: 0.056 miles of BRIDGE & APPROACHES

Roadway Items:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF BRIDGE (STA 10+86)	1.000	UN
REMOVAL OF ASPHALT (ALL DEPTHS)	372.000	SY
REMOVE AND RELAY RIPRAP	500.000	SY
UNCLASSIFIED EXCAVATION (FM)	640.000	CY
EXCESS EXCAVATION (FM)	195.000	CY
CRUSHED STONE, SIZE 610	207.000	TON
RIGHT-OF-WAY MARKERS (TYPE I)	6.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA

EROSION CONTROL ITEMS:

COMMERCIAL FERTILIZER (13:13:13)	0.300	TON
AMMONIUM NITRATE	0.030	TON
SEEDING	0.300	AC
VEGETATIVE MATERIALS FOR MULCH	0.900	TON
EXCELSIOR BLANKET	900.000	SY
TEMPORARY SILT FENCE (TYPE I) (AOS 0.15 mm - 0.84 mm)	400.000	LF
WATTLES, 20"	60.000	LF
LOOSE RIPRAP, 300 LB.	40.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, NON-WOVEN AOS < 0.43 mm	200.000	SY

BRIDGE ITEMS:

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14" STEEL PILING	760.000	LF
18" PRE-FORMED PILE HOLES	190.000	LF
BRIDGE CONCRETE, CLASS "A"	67.000	CY
REINFORCEMENT	10,111.000	LB
31' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR, 30 DEG SKEW, RT FWD	6.000	EA
40' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR, 30 DEG SKEW, RT FWD	12.000	EA
31' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR, 30 DEG SKEW, RT FWD	2.000	EA
40' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR, 30 DEG SKEW, RT FWD	4.000	EA
PRECAST CONCRETE BARRIER RAIL	222.000	LF

STRUCTURAL STEEL	4,329.000	LB
LOOSE RIPRAP, 300 LB.	252.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, NON-WOVEN AOS < 0.43 mm	500.000	SY