OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS

County Newton
Project No. LSBP-51(16)
Road Name. Buckley Road

BIDS RECEIVED: FRIDAY, DECEMBER 18, 2026 AT 10:00 AM IN THE BOARDROOM AT DECATUR, MS
Project Description: 0.161 miles of BRIDGE & APPROACHES

Roadway Items:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF RAILROAD FLAT CAR BRIDGE @ STATION 14+90.04	1.000	LS
REMOVAL OF PIPE (ALL SIZES)	78.000	LF
UNCLASSIFIED EXCAVATION (FM)	606.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9)	7,797.000	CY
CRUSHED STONE, SIZE 825	951.000	TON
18" REINFORCED CONCRETE PIPE, CLASS III	72.000	LF
GUARD RAIL, "W" BEAM	75.000	LF
GUARD RAIL, BRIDGE END SECTION, THRIE BEAM	4.000	EA
GUARD RAIL, TERMINAL END SECTION	4.000	EA
ROADWAY CONSTRUCTION SURVEYING	1.000	LS
RIGHT-OF-WAY MARKERS (TYPE II)	10.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA
REFLECTORIZED TRAFFIC DELINEATOR SIGN (ENCAPSULATED LENS)	18.000	EA
GEOTEXTILE UNDER BRIDGE END TREATMENT, NON-WOVEN, TYPE V, AOS < 0.43	168.000	SY

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	4.000	TON
COMMERCIAL FERTILIZER (13:13:13)	2.000	TON
SEEDING	2.000	AC
VEGETATIVE MATERIALS FOR MULCH	4.000	TON
SOLID SODDING	50.000	SY
TEMPORARY GRASSING	2.000	AC
PORTLAND CEMENT CONCRETE PAVED DITCH	5.750	CY
EROSION MAT	39.000	SY
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	1,837.000	LF
WATTLES, 20"	300.000	LF

BRIDGE ITEMS:

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14 " PRESTRESSED CONCRETE PILING	680.000	LF
18 " PRESTRESSED CONCRETE PILING	855.000	LF

18 " PRE-FORMED PILE HOLES	541.000	LF
24 " PRE-FORMED PILE HOLES	632.000	LF
BRIDGE CONCRETE, CLASS A	204.000	CY
40 ' PRESTRESSED CONCRETE BEAM, TYPE I & II	397.500	LF
100 ' PRESTRESSED CONCRETE BEAM TYPE IV	498.750	LF
REINFORCEMENT	36,082.000	LB
CONCRETE RAILING	360.000	LF
LOOSE RIPRAP, 300 LB.	343.000	TON
GEOTEXTILE UNDER RIPRAP, NON-WOVEN, TYPE V, AOS < 0.43	695.000	SY