



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County	Oktibbeha
Project No.	LSBP-53(18)
Road Name.	Sherman Drive

BIDS RECEIVED: THURSDAY, AUGUST 20, 2026 AT 10:00 AM IN THE SUPERVISOR'S BOARDROOM AT STARKVILLE, MS

Project Description: 0.128 miles of BOX BRIDGE and APPROACHES

ROADWAY ITEMS:

Mobilization	1.000	LS
Clearing and Grubbing	1.000	LS
Removal of Bridge @ STA. 502+41	1.000	UN
Removal of Pipe (All Sizes)	30.000	LF
Unclassified Excavation (FM)	3,931.000	CY
Borrow Excavation (F.M.E.) (Contractor Furnished) (Class 9)	756.000	CY
Granular Material (FM), (Class 3, Group C)	413.000	CY
Right-of-Way Markers (Type I)	18.000	EA
Maintenance of Traffic	1.000	LS
Additional Construction Signs	0.000	SF

EROSION CONTROL ITEMS:

Agricultural Limestone	3.020	TON
Commercial Fertilizer (13: 13: 13)	1.510	TON
Seeding	1.510	AC
Vegetative Materials for Mulch	4.530	TON
Temporary Silt Fence (Type I) (AOS 0.15-0.84)	220.000	LF
Wattles, 20"	300.000	LF

BOX BRIDGE ITEMS:

Box Bridge Concrete, Class "BB"	350.290	CY
Reinforcement	67,834.000	LB
Loose Riprap (200LB.)	85.000	TON
Geotextile under Riprap, Type V, Non-Woven, AOS <0.43	170.000	SY