



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County Oktibbeha
Project No. LSBP-53(19)
Road Name. Osborn Road

BIDS RECEIVED: THURSDAY, MAY 14, 2026 AT 10:00 AM IN THE SUPERVISOR'S BOARDROOM AT STARKVILLE, MS

Project Description: 0.083 miles of BRIDGE and APPROACHES

ROADWAY ITEMS:

	QUANTITY	UNIT
Mobilization	1.000	LS
Clearing and Grubbing	1.000	LS
Removal of Precast Bridge @ Sta. 6+72	1.000	UN
Unclassified Excavation (FM)	100.000	CY
Borrow Excavation (Contractor-Furnished FME, Class 9)	200.000	CY
Granular Material (FM), (Class 3, Group B)	275.000	CY
Right-of-Way Markers (type 1)	10.000	EA
Maintenance of Traffic	1.000	LS
Additional Construction Signs	0.000	SF
Reflectorized Traffic Warning Sign (Encapsulated Lens)	4.000	EA

EROSION CONTROL ITEMS:

	QUANTITY	UNIT
Agricultural Limestone	0.780	TON
Commercial Fertilizer (13:13:13)	0.390	TON
Seeding	0.390	AC
Vegetative Materials For Mulch	1.170	TON
Temporary Silt Fence (Type 1) (AOS 0.15-0.84)	805.000	LF
Wattles, 20"	140.000	LF
Loose Riprap, 200 Lb.	110.000	TON
Geotextile under Riprap, Type V, AOS <0.43	103.000	SY

BRIDGE ITEMS:

	QUANTITY	UNIT
Test Pile, 12" Steel	2.000	EA
Conventional Static Pile Load Test	0.000	EA
12" Steel Piling	450.000	LF
16" Preformed Pile Hole	300.000	LF
Bridge Concrete, Class B	4.000	CY
Reinforcement	72.000	LB
19' Precast Concrete Slab Unit, 3.5' Interior	12.000	EA
31' Precast Concrete Slab Unit, 3.5' Interior	6.000	EA
19' Precast Concrete Slab Unit, Curb	4.000	EA
31' Precast Concrete Slab Unit, Curb	2.000	EA
Beam-Type Railing with Concrete and Steel Posts	138.000	LF
29' Precast Concrete Cap, Intermediate Unit, Steel Pile	2.000	EA
29' Precast Concrete Cap, End Unit, Steel Pile	2.000	EA
7.5' Precast Concrete Wing	4.000	EA

Loose Riprap, 300 Lb.

146.000

TON

Geotextile under Riprap, Type V, AOS <0.43

216.000

SY